


32		1257.28	944.08	2954.4	200.00	5,098.52	12,712.47	360.00	13,856.61
32-1401南主层南外墙漏水		314.32	161.02	738.6	50.00	1,274.63	3,739.32	90.00	4,075.86
窗口打胶		95.13	65.32	12.41	5.00	181.50	181.50	9.00	197.84
窗口原密封胶铲除，重新打硅宝结构耐候胶		95.13	65.32	12.41	5.00	181.50	181.50	9.00	197.84
堵漏		97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
采用YH东方雨虹对缝隙堵漏		97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
接缝处打胶		11.65	14.51	4.21	5.00	31.89	252.57	9.00	275.30
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝		11.65	14.51	4.21	5.00	31.89	252.57	9.00	275.30
垃圾清理		13.16		3.52	5.00	17.51	122.57	9.00	133.60
人工清理建筑垃圾并装袋，垂直运输短驳		13.16		3.52	5.00	17.51	122.57	9.00	133.60
垃圾装车外运		31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25cm以内）		31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平		14.36	8.25	2.13	5.00	25.98	308.64	9.00	336.42
采用立邦抗裂耐水砂浆，对墙面进行找平		14.36	8.25	2.13	5.00	25.98	308.64	9.00	336.42
涂刷防水涂料2遍		19.86	11.76	2.13	5.00	35.44	771.88	9.00	841.35
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm		19.86	11.76	2.13	5.00	35.44	771.88	9.00	841.35
涂刷界面剂		4.77	7.65	1.26	5.00	14.36	284.33	9.00	309.92
德高界面处理剂		4.77	7.65	1.26	5.00	14.36	284.33	9.00	309.92
外墙表面铲除清理		14.73		2.43	5.00	18.02	356.80	9.00	388.91
对原墙面落灰、起皮的地方进行铲除		14.73		2.43	5.00	18.02	356.80	9.00	388.91
外墙涂料		12.13	8.16	1.97	5.00	23.37	534.47	9.00	582.57
外墙溶剂涂料一底二面		12.13	8.16	1.97	5.00	23.37	534.47	9.00	582.57
32-201南卧室外墙漏水		314.32	161.02	738.6	50.00	1,274.63	3,187.47	90.00	3,474.34
窗口打胶		95.13	65.32	12.41	5.00	181.50	363.00	9.00	395.67
窗口原密封胶铲除，重新打硅宝结构耐候胶		95.13	65.32	12.41	5.00	181.50	363.00	9.00	395.67
堵漏		97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
采用YH东方雨虹对缝隙堵漏		97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
接缝处打胶		11.65	14.51	4.21	5.00	31.89	172.21	9.00	187.71
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝		11.65	14.51	4.21	5.00	31.89	172.21	9.00	187.71
垃圾清理		13.16		3.52	5.00	17.51	87.55	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳		13.16		3.52	5.00	17.51	87.55	9.00	95.43
垃圾装车外运		31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25cm以内）		31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平		14.36	8.25	2.13	5.00	25.98	210.44	9.00	229.38
采用立邦抗裂耐水砂浆，对墙面进行找平		14.36	8.25	2.13	5.00	25.98	210.44	9.00	229.38
涂刷防水涂料2遍		19.86	11.76	2.13	5.00	35.44	574.13	9.00	625.80
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm		19.86	11.76	2.13	5.00	35.44	574.13	9.00	625.80
涂刷界面剂		4.77	7.65	1.26	5.00	14.36	193.86	9.00	211.31
德高界面处理剂		4.77	7.65	1.26	5.00	14.36	193.86	9.00	211.31
外墙表面铲除清理		14.73		2.43	5.00	18.02	243.27	9.00	265.16
对原墙面落灰、起皮的地方进行铲除		14.73		2.43	5.00	18.02	243.27	9.00	265.16
外墙涂料		12.13	8.16	1.97	5.00	23.37	416.45	9.00	453.93
外墙溶剂涂料一底二面		12.13	8.16	1.97	5.00	23.37	416.45	9.00	453.93
32-502南卧室外墙漏水		314.32	161.02	738.6	50.00	1,274.63	2,461.95	90.00	2,705.34
窗口打胶		95.13	65.32	12.41	5.00	181.50	363.00	9.00	395.67
窗口原密封胶铲除，重新打硅宝结构耐候胶		95.13	65.32	12.41	5.00	181.50	363.00	9.00	395.67
堵漏		97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
采用YH东方雨虹对缝隙堵漏		97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
接缝处打胶		11.65	14.51	4.21	5.00	31.89	108.43	9.00	118.19
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝		11.65	14.51	4.21	5.00	31.89	108.43	9.00	118.19
垃圾清理		13.16		3.52	5.00	17.51	52.53	9.00	57.26
人工清理建筑垃圾并装袋，垂直运输短驳		13.16		3.52	5.00	17.51	52.53	9.00	57.26



垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平	14.36	8.25	2.13	5.00	25.98	132.50	9.00	144.43
采用立邦抗裂耐水砂浆，对墙面进行找平	14.36	8.25	2.13	5.00	25.98	132.50	9.00	144.43
涂刷防水涂料2遍	19.86	11.76	2.13	5.00	35.44	361.49	9.00	394.02
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm	19.86	11.76	2.13	5.00	35.44	361.49	9.00	394.02
涂刷界面剂	4.77	7.65	1.26	5.00	14.36	122.06	9.00	133.05
提高界面处理剂	4.77	7.65	1.26	5.00	14.36	122.06	9.00	133.05
外墙表面铲除清理	14.73		2.43	5.00	18.02	153.17	9.00	166.96
对原墙面落灰、起皮的地方进行铲除	14.73		2.43	5.00	18.02	153.17	9.00	166.96
外墙涂料	12.13	8.16	1.97	5.00	23.37	262.21	9.00	285.81
外墙溶剂涂料一底二面	12.13	8.16	1.97	5.00	23.37	262.21	9.00	285.81
32-701主卧东外墙翻水	314.32	161.02	738.6	50.00	1,274.63	3,303.73	90.00	3,601.07
窗口打胶	95.13	65.32	12.41	5.00	181.50	181.50	9.00	197.84
窗口原密封胶铲除，重新打硅宝结构耐候胶	95.13	65.32	12.41	5.00	181.50	181.50	9.00	197.84
堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
采用YH东方雨虹对缝阻堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
接缝处打胶	11.65	14.51	4.21	5.00	31.89	210.47	9.00	229.41
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝	11.65	14.51	4.21	5.00	31.89	210.47	9.00	229.41
垃圾清理	13.16		3.52	5.00	17.51	105.06	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	105.06	9.00	114.52
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平	14.36	8.25	2.13	5.00	25.98	257.20	9.00	280.35
采用立邦抗裂耐水砂浆，对墙面进行找平	14.36	8.25	2.13	5.00	25.98	257.20	9.00	280.35
涂刷防水涂料2遍	19.86	11.76	2.13	5.00	35.44	643.24	9.00	701.13
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm	19.86	11.76	2.13	5.00	35.44	643.24	9.00	701.13
涂刷界面剂	4.77	7.65	1.26	5.00	14.36	236.94	9.00	258.26
提高界面处理剂	4.77	7.65	1.26	5.00	14.36	236.94	9.00	258.26
外墙表面铲除清理	14.73		2.43	5.00	18.02	297.33	9.00	324.09
对原墙面落灰、起皮的地方进行铲除	14.73		2.43	5.00	18.02	297.33	9.00	324.09
外墙涂料	12.13	8.16	1.97	5.00	23.37	445.43	9.00	485.62
外墙溶剂涂料一底二面	12.13	8.16	1.97	5.00	23.37	445.43	9.00	485.62

