

天鹄湖花园B区房屋渗水维修工程预算

行标签	求和项:数量	求和项:人工	求和项:主材	求和项:机械辅材	求和项:不含税单价	平均值项:综合取费	平均值项:税率	求和项:含税价
130	8222.81	17587.86	16835.2	19465.46	56,582.71	5.00	9.00	360,031.82
130-1102厨房南外墙漏水	67.43	364.21	391.87	402.61	1,216.62	5.00	9.00	3,106.37
表面清理	11.5	15.56		2.43	18.89	5.00	9.00	236.79
对原墙面落灰、起皮的地方进行铲除	11.5	15.56		2.43	18.89	5.00	9.00	236.79
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除,重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	3.45	12	15	4	32.55	5.00	9.00	122.41
对窗台与外墙面接缝处,原密封胶铲除,重新打胶	3.45	12	15	4	32.55	5.00	9.00	122.41
垃圾清理	4	13.16		3.52	17.51	5.00	9.00	76.34
人工清理建筑垃圾并装袋,垂直运输短驳	4	13.16		3.52	17.51	5.00	9.00	76.34
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土(8t以内)(运距25km以内)	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	6.9	20.66	10.51	2.33	35.18	5.00	9.00	264.59
采用3mm立邦抗裂防水砂浆,对墙面进行找平	6.9	20.66	10.51	2.33	35.18	5.00	9.00	264.59
涂刷防水涂料2遍	12.65	28.6	21.2	2.13	54.53	5.00	9.00	751.88
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	12.65	28.6	21.2	2.13	54.53	5.00	9.00	751.88
涂刷界面剂	12.65	4.77	7.65	1.26	14.36	5.00	9.00	198.00
德高界面处理剂	12.65	4.77	7.65	1.26	14.36	5.00	9.00	198.00
外墙涂料	13.28	8.56	12.16	1.97	23.82	5.00	9.00	344.80
外墙溶剂涂料一底二面	13.28	8.56	12.16	1.97	23.82	5.00	9.00	344.80
130-1201北客厅北外墙漏水	90.54	364.21	391.87	402.61	1,216.62	5.00	9.00	3,493.16
表面清理	15.6	15.56		2.43	18.89	5.00	9.00	321.20
对原墙面落灰、起皮的地方进行铲除	15.6	15.56		2.43	18.89	5.00	9.00	321.20
窗口打胶	0	95.17	190.21	12.41	312.68	5.00	9.00	0.00
窗口原密封胶铲除,重新打硅宝结构耐候胶	0	95.17	190.21	12.41	312.68	5.00	9.00	0.00
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.68	12	15	4	32.55	5.00	9.00	166.04
对窗台与外墙面接缝处,原密封胶铲除,重新打胶	4.68	12	15	4	32.55	5.00	9.00	166.04
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	95.43
人工清理建筑垃圾并装袋,垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	95.43
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土(8t以内)(运距25km以内)	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	9.36	20.66	10.51	2.33	35.18	5.00	9.00	358.92
采用3mm立邦抗裂防水砂浆,对墙面进行找平	9.36	20.66	10.51	2.33	35.18	5.00	9.00	358.92
涂刷防水涂料2遍	17.16	28.6	21.2	2.13	54.53	5.00	9.00	1,019.95
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	17.16	28.6	21.2	2.13	54.53	5.00	9.00	1,019.95
涂刷界面剂	18.72	4.77	7.65	1.26	14.36	5.00	9.00	293.01
德高界面处理剂	18.72	4.77	7.65	1.26	14.36	5.00	9.00	293.01
外墙涂料	18.02	8.56	12.16	1.97	23.82	5.00	9.00	467.87
外墙溶剂涂料一底二面	18.02	8.56	12.16	1.97	23.82	5.00	9.00	467.87
130-1201北卧室北外墙漏水	88.86	364.21	391.87	402.61	1,216.62	5.00	9.00	3,749.73
表面清理	15.1	15.56		2.43	18.89	5.00	9.00	310.91
对原墙面落灰、起皮的地方进行铲除	15.1	15.56		2.43	18.89	5.00	9.00	310.91
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除,重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.53	12	15	4	32.55	5.00	9.00	160.72
对窗台与外墙面接缝处,原密封胶铲除,重新打胶	4.53	12	15	4	32.55	5.00	9.00	160.72
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	95.43
人工清理建筑垃圾并装袋,垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	95.43
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土(8t以内)(运距25km以内)	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	9.06	20.66	10.51	2.33	35.18	5.00	9.00	347.42
采用3mm立邦抗裂防水砂浆,对墙面进行找平	9.06	20.66	10.51	2.33	35.18	5.00	9.00	347.42
涂刷防水涂料2遍	16.61	28.6	21.2	2.13	54.53	5.00	9.00	987.26
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	16.61	28.6	21.2	2.13	54.53	5.00	9.00	987.26
涂刷界面剂	18.12	4.77	7.65	1.26	14.36	5.00	9.00	283.62
德高界面处理剂	18.12	4.77	7.65	1.26	14.36	5.00	9.00	283.62
外墙涂料	17.44	8.56	12.16	1.97	23.82	5.00	9.00	452.81
外墙溶剂涂料一底二面	17.44	8.56	12.16	1.97	23.82	5.00	9.00	452.81
130-1201南客厅南外墙漏水	98.86	364.21	391.87	402.61	1,216.62	5.00	9.00	4,078.85
表面清理	17.1	15.56		2.43	18.89	5.00	9.00	352.09
对原墙面落灰、起皮的地方进行铲除	17.1	15.56		2.43	18.89	5.00	9.00	352.09
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除,重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.13	12	15	4	32.55	5.00	9.00	182.01
对窗台与外墙面接缝处,原密封胶铲除,重新打胶	5.13	12	15	4	32.55	5.00	9.00	182.01
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋,垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土(8t以内)(运距25km以内)	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	10.26	20.66	10.51	2.33	35.18	5.00	9.00	393.44

采用3mm立邦抗裂耐水砂浆，对墙面进行找平	10.26	20.66	10.51	2.33	35.18	5.00	9.00	393.44
涂刷防水涂料2遍	18.81	28.6	21.2	2.13	54.53	5.00	9.00	1,118.02
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	18.81	28.6	21.2	2.13	54.53	5.00	9.00	1,118.02
涂刷界面剂	18.81	4.77	7.65	1.26	14.36	5.00	9.00	294.42
德高界面处理剂	18.81	4.77	7.65	1.26	14.36	5.00	9.00	294.42
外墙涂料	19.75	8.56	12.16	1.97	23.82	5.00	9.00	512.79
外墙溶剂涂料一底二面	19.75	8.56	12.16	1.97	23.82	5.00	9.00	512.79
130-1201南主卧南外墙漏水	109.9	364.21	391.87	402.61	1,216.62	5.00	9.00	4,429.29
表面清理	19.2	15.56		2.43	18.89	5.00	9.00	395.33
对原墙面落灰、起皮的地方进行铲除	19.2	15.56		2.43	18.89	5.00	9.00	395.33
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.76	12	15	4	32.55	5.00	9.00	204.36
对窗台与外墙面接缝处，原密封胶铲除，重新打	5.76	12	15	4	32.55	5.00	9.00	204.36
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	11.52	20.66	10.51	2.33	35.18	5.00	9.00	441.74
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	11.52	20.66	10.51	2.33	35.18	5.00	9.00	441.74
涂刷防水涂料2遍	21.12	28.6	21.2	2.13	54.53	5.00	9.00	1,255.32
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.12	28.6	21.2	2.13	54.53	5.00	9.00	1,255.32
涂刷界面剂	21.12	4.77	7.65	1.26	14.36	5.00	9.00	330.58
德高界面处理剂	21.12	4.77	7.65	1.26	14.36	5.00	9.00	330.58
外墙涂料	22.18	8.56	12.16	1.97	23.82	5.00	9.00	575.88
外墙溶剂涂料一底二面	22.18	8.56	12.16	1.97	23.82	5.00	9.00	575.88
130-1403厨房南外墙漏水	69.12	364.21	391.87	402.61	1,216.62	5.00	9.00	3,141.31
表面清理	11.6	15.56		2.43	18.89	5.00	9.00	238.84
对原墙面落灰、起皮的地方进行铲除	11.6	15.56		2.43	18.89	5.00	9.00	238.84
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	3.48	12	15	4	32.55	5.00	9.00	123.46
对窗台与外墙面接缝处，原密封胶铲除，重新打	3.48	12	15	4	32.55	5.00	9.00	123.46
垃圾清理	4	13.16		3.52	17.51	5.00	9.00	76.34
人工清理建筑垃圾并装袋，垂直运输短驳	4	13.16		3.52	17.51	5.00	9.00	76.34
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	6.96	20.66	10.51	2.33	35.18	5.00	9.00	266.89
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	6.96	20.66	10.51	2.33	35.18	5.00	9.00	266.89
涂刷防水涂料2遍	12.76	28.6	21.2	2.13	54.53	5.00	9.00	758.42
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	12.76	28.6	21.2	2.13	54.53	5.00	9.00	758.42
涂刷界面剂	13.92	4.77	7.65	1.26	14.36	5.00	9.00	217.88
德高界面处理剂	13.92	4.77	7.65	1.26	14.36	5.00	9.00	217.88
外墙涂料	13.4	8.56	12.16	1.97	23.82	5.00	9.00	347.92
外墙溶剂涂料一底二面	13.4	8.56	12.16	1.97	23.82	5.00	9.00	347.92
130-1503南卧室南外墙漏水	98.36	364.21	391.87	402.61	1,216.62	5.00	9.00	4,306.45
表面清理	16.5	15.56		2.43	18.89	5.00	9.00	339.54
对原墙面落灰、起皮的地方进行铲除	16.5	15.56		2.43	18.89	5.00	9.00	339.54
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	2	115.73	135.14	12.56	276.60	5.00	9.00	602.99
采用YH东方雨虹对缝堵漏	2	115.73	135.14	12.56	276.60	5.00	9.00	602.99
接缝处打胶	4.95	12	15	4	32.55	5.00	9.00	175.62
对窗台与外墙面接缝处，原密封胶铲除，重新打	4.95	12	15	4	32.55	5.00	9.00	175.62
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	9.9	20.66	10.51	2.33	35.18	5.00	9.00	379.63
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	9.9	20.66	10.51	2.33	35.18	5.00	9.00	379.63
涂刷防水涂料2遍	18.15	28.6	21.2	2.13	54.53	5.00	9.00	1,078.79
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	18.15	28.6	21.2	2.13	54.53	5.00	9.00	1,078.79
涂刷界面剂	19.8	4.77	7.65	1.26	14.36	5.00	9.00	309.92
德高界面处理剂	19.8	4.77	7.65	1.26	14.36	5.00	9.00	309.92
外墙涂料	19.06	8.56	12.16	1.97	23.82	5.00	9.00	494.87
外墙溶剂涂料一底二面	19.06	8.56	12.16	1.97	23.82	5.00	9.00	494.87
130-1601南主卧外墙漏水	111.28	364.21	391.87	402.61	1,216.62	5.00	9.00	4,442.39
表面清理	19.1	15.56		2.43	18.89	5.00	9.00	393.27
对原墙面落灰、起皮的地方进行铲除	19.1	15.56		2.43	18.89	5.00	9.00	393.27
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.73	12	15	4	32.55	5.00	9.00	203.30
对窗台与外墙面接缝处，原密封胶铲除，重新打	5.73	12	15	4	32.55	5.00	9.00	203.30
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52



人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	11.46	20.66	10.51	2.33	35.18	5.00	9.00	439.44
采用3mm立邦抗裂防水砂浆，对墙面进行找平	11.46	20.66	10.51	2.33	35.18	5.00	9.00	439.44
涂刷防水涂料2遍	21.01	28.6	21.2	2.13	54.53	5.00	9.00	1,248.79
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.01	28.6	21.2	2.13	54.53	5.00	9.00	1,248.79
涂刷界面剂	22.92	4.77	7.65	1.26	14.36	5.00	9.00	358.75
德高界面处理剂	22.92	4.77	7.65	1.26	14.36	5.00	9.00	358.75
外墙涂料	22.06	8.56	12.16	1.97	23.82	5.00	9.00	572.76
外墙溶剂涂料一底二面	22.06	8.56	12.16	1.97	23.82	5.00	9.00	572.76
130-1603南卧室外墙	108.9	364.21	391.87	402.61	1,216.62	5.00	9.00	4,088.47
表面清理	19.2	15.56		2.43	18.89	5.00	9.00	395.33
对原墙面落灰、起皮的地方进行铲除	19.2	15.56		2.43	18.89	5.00	9.00	395.33
窗口打胶	0	95.17	190.21	12.41	312.68	5.00	9.00	0.00
窗口原密封胶铲除，重新打硅宝结构耐候胶	0	95.17	190.21	12.41	312.68	5.00	9.00	0.00
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.76	12	15	4	32.55	5.00	9.00	204.36
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.76	12	15	4	32.55	5.00	9.00	204.36
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
抹灰	11.52	20.66	10.51	2.33	35.18	5.00	9.00	441.74
水泥砂浆抹灰	11.52	20.66	10.51	2.33	35.18	5.00	9.00	441.74
涂刷防水涂料2遍	21.12	28.6	21.2	2.13	54.53	5.00	9.00	1,255.32
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.12	28.6	21.2	2.13	54.53	5.00	9.00	1,255.32
涂刷界面剂	21.12	4.77	7.65	1.26	14.36	5.00	9.00	330.58
德高界面处理剂	21.12	4.77	7.65	1.26	14.36	5.00	9.00	330.58
外墙涂料	22.18	8.56	12.16	1.97	23.82	5.00	9.00	575.88
外墙溶剂涂料一底二面	22.18	8.56	12.16	1.97	23.82	5.00	9.00	575.88
130-1703南主卧室南外墙漏水	111.82	364.21	391.87	402.61	1,216.62	5.00	9.00	4,459.34
表面清理	19.2	15.56		2.43	18.89	5.00	9.00	395.33
对原墙面落灰、起皮的地方进行铲除	19.2	15.56		2.43	18.89	5.00	9.00	395.33
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.76	12	15	4	32.55	5.00	9.00	204.36
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.76	12	15	4	32.55	5.00	9.00	204.36
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	11.52	20.66	10.51	2.33	35.18	5.00	9.00	441.74
采用3mm立邦抗裂防水砂浆，对墙面进行找平	11.52	20.66	10.51	2.33	35.18	5.00	9.00	441.74
涂刷防水涂料2遍	21.12	28.6	21.2	2.13	54.53	5.00	9.00	1,255.32
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.12	28.6	21.2	2.13	54.53	5.00	9.00	1,255.32
涂刷界面剂	23.04	4.77	7.65	1.26	14.36	5.00	9.00	360.63
德高界面处理剂	23.04	4.77	7.65	1.26	14.36	5.00	9.00	360.63
外墙涂料	22.18	8.56	12.16	1.97	23.82	5.00	9.00	575.88
外墙溶剂涂料一底二面	22.18	8.56	12.16	1.97	23.82	5.00	9.00	575.88
130-1802南卧室外墙	108.37	364.21	391.87	402.61	1,216.62	5.00	9.00	4,071.67
表面清理	19.1	15.56		2.43	18.89	5.00	9.00	393.27
对原墙面落灰、起皮的地方进行铲除	19.1	15.56		2.43	18.89	5.00	9.00	393.27
窗口打胶	0	95.17	190.21	12.41	312.68	5.00	9.00	0.00
窗口原密封胶铲除，重新打硅宝结构耐候胶	0	95.17	190.21	12.41	312.68	5.00	9.00	0.00
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.73	12	15	4	32.55	5.00	9.00	203.30
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.73	12	15	4	32.55	5.00	9.00	203.30
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
抹灰	11.46	20.66	10.51	2.33	35.18	5.00	9.00	439.44
水泥砂浆抹灰	11.46	20.66	10.51	2.33	35.18	5.00	9.00	439.44
涂刷防水涂料2遍	21.01	28.6	21.2	2.13	54.53	5.00	9.00	1,248.79
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.01	28.6	21.2	2.13	54.53	5.00	9.00	1,248.79
涂刷界面剂	21.01	4.77	7.65	1.26	14.36	5.00	9.00	328.85
德高界面处理剂	21.01	4.77	7.65	1.26	14.36	5.00	9.00	328.85
外墙涂料	22.06	8.56	12.16	1.97	23.82	5.00	9.00	572.76
外墙溶剂涂料一底二面	22.06	8.56	12.16	1.97	23.82	5.00	9.00	572.76
130-1803南主卧室南外墙漏水	111.28	364.21	391.87	402.61	1,216.62	5.00	9.00	4,442.39
表面清理	19.1	15.56		2.43	18.89	5.00	9.00	393.27
对原墙面落灰、起皮的地方进行铲除	19.1	15.56		2.43	18.89	5.00	9.00	393.27
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49

采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.73	12	15	4	32.55	5.00	9.00	203.30
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.73	12	15	4	32.55	5.00	9.00	203.30
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	11.46	20.66	10.51	2.33	35.18	5.00	9.00	439.44
采用3mm立邦抗裂防水砂浆，对墙面进行找平	11.46	20.66	10.51	2.33	35.18	5.00	9.00	439.44
涂刷防水涂料2遍	21.01	28.6	21.2	2.13	54.53	5.00	9.00	1,248.79
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.01	28.6	21.2	2.13	54.53	5.00	9.00	1,248.79
涂刷界面剂	22.92	4.77	7.65	1.26	14.36	5.00	9.00	358.75
德高界面处理剂	22.92	4.77	7.65	1.26	14.36	5.00	9.00	358.75
外墙涂料	22.06	8.56	12.16	1.97	23.82	5.00	9.00	572.76
外墙溶剂涂料一底二面	22.06	8.56	12.16	1.97	23.82	5.00	9.00	572.76
130-2001南主卧外墙漏水	114.96	364.21	391.87	402.61	1,216.62	5.00	9.00	4,545.74
表面清理	19.6	15.56		2.43	18.89	5.00	9.00	403.56
对原墙面落灰、起皮的地方进行铲除	19.6	15.56		2.43	18.89	5.00	9.00	403.56
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.88	12	15	4	32.55	5.00	9.00	208.62
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.88	12	15	4	32.55	5.00	9.00	208.62
垃圾清理	7	13.16		3.52	17.51	5.00	9.00	133.60
人工清理建筑垃圾并装袋，垂直运输短驳	7	13.16		3.52	17.51	5.00	9.00	133.60
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	11.76	20.66	10.51	2.33	35.18	5.00	9.00	450.95
采用3mm立邦抗裂防水砂浆，对墙面进行找平	11.76	20.66	10.51	2.33	35.18	5.00	9.00	450.95
涂刷防水涂料2遍	21.56	28.6	21.2	2.13	54.53	5.00	9.00	1,281.48
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.56	28.6	21.2	2.13	54.53	5.00	9.00	1,281.48
涂刷界面剂	23.52	4.77	7.65	1.26	14.36	5.00	9.00	368.15
德高界面处理剂	23.52	4.77	7.65	1.26	14.36	5.00	9.00	368.15
外墙涂料	22.64	8.56	12.16	1.97	23.82	5.00	9.00	587.82
外墙溶剂涂料一底二面	22.64	8.56	12.16	1.97	23.82	5.00	9.00	587.82
130-2003北次卧外墙	97.28	364.21	391.87	402.61	1,216.62	5.00	9.00	4,028.67
表面清理	16.8	15.56		2.43	18.89	5.00	9.00	345.91
对原墙面落灰、起皮的地方进行铲除	16.8	15.56		2.43	18.89	5.00	9.00	345.91
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.04	12	15	4	32.55	5.00	9.00	178.81
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.04	12	15	4	32.55	5.00	9.00	178.81
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
抹灰	10.08	20.66	10.51	2.33	35.18	5.00	9.00	386.52
水泥砂浆抹灰	10.08	20.66	10.51	2.33	35.18	5.00	9.00	386.52
涂刷防水涂料2遍	18.48	28.6	21.2	2.13	54.53	5.00	9.00	1,098.40
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	18.48	28.6	21.2	2.13	54.53	5.00	9.00	1,098.40
涂刷界面剂	18.48	4.77	7.65	1.26	14.36	5.00	9.00	289.25
德高界面处理剂	18.48	4.77	7.65	1.26	14.36	5.00	9.00	289.25
外墙涂料	19.4	8.56	12.16	1.97	23.82	5.00	9.00	503.70
外墙溶剂涂料一底二面	19.4	8.56	12.16	1.97	23.82	5.00	9.00	503.70
130-2003北客厅北外墙漏水	97.36	364.21	391.87	402.61	1,216.62	5.00	9.00	4,004.65
表面清理	16.5	15.56		2.43	18.89	5.00	9.00	339.74
对原墙面落灰、起皮的地方进行铲除	16.5	15.56		2.43	18.89	5.00	9.00	339.74
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.95	12	15	4	32.55	5.00	9.00	175.62
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	4.95	12	15	4	32.55	5.00	9.00	175.62
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	9.9	20.66	10.51	2.33	35.18	5.00	9.00	379.63
采用3mm立邦抗裂防水砂浆，对墙面进行找平	9.9	20.66	10.51	2.33	35.18	5.00	9.00	379.63
涂刷防水涂料2遍	18.15	28.6	21.2	2.13	54.53	5.00	9.00	1,078.79
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	18.15	28.6	21.2	2.13	54.53	5.00	9.00	1,078.79
涂刷界面剂	19.8	4.77	7.65	1.26	14.36	5.00	9.00	309.92
德高界面处理剂	19.8	4.77	7.65	1.26	14.36	5.00	9.00	309.92
外墙涂料	19.06	8.56	12.16	1.97	23.82	5.00	9.00	494.87
外墙溶剂涂料一底二面	19.06	8.56	12.16	1.97	23.82	5.00	9.00	494.87
130-2003北客厅阳台外墙	96.23	364.21	391.87	402.61	1,216.62	5.00	9.00	3,995.36
表面清理	16.6	15.56		2.43	18.89	5.00	9.00	341.79

对原墙面落灰、起皮的地方进行铲除	16.6	15.56		2.43	18.89	5.00	9.00	341.79
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.98	12	15	4	32.55	5.00	9.00	176.69
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	4.98	12	15	4	32.55	5.00	9.00	176.69
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
抹灰	9.96	20.66	10.51	2.33	35.18	5.00	9.00	381.93
水泥砂浆抹灰	9.96	20.66	10.51	2.33	35.18	5.00	9.00	381.93
涂刷防水涂料2遍	18.26	28.6	21.2	2.13	54.53	5.00	9.00	1,085.33
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	18.26	28.6	21.2	2.13	54.53	5.00	9.00	1,085.33
涂刷界面剂	18.26	4.77	7.65	1.26	14.36	5.00	9.00	285.81
德高界面处理剂	18.26	4.77	7.65	1.26	14.36	5.00	9.00	285.81
外墙涂料	19.17	8.56	12.16	1.97	23.82	5.00	9.00	497.73
外墙溶剂涂料一底二面	19.17	8.56	12.16	1.97	23.82	5.00	9.00	497.73
130-2401北阳台北外墙	90	364.21	391.87	402.61	1,216.62	5.00	9.00	3,476.23
表面清理	15.5	15.56		2.43	18.89	5.00	9.00	319.15
对原墙面落灰、起皮的地方进行铲除	15.5	15.56		2.43	18.89	5.00	9.00	319.15
窗口打胶	0	95.17	190.21	12.41	312.68	5.00	9.00	0.00
窗口原密封胶铲除，重新打硅宝结构耐候胶	0	95.17	190.21	12.41	312.68	5.00	9.00	0.00
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.65	12	15	4	32.55	5.00	9.00	164.98
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	4.65	12	15	4	32.55	5.00	9.00	164.98
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	95.43
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	9.3	20.66	10.51	2.33	35.18	5.00	9.00	356.62
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	9.3	20.66	10.51	2.33	35.18	5.00	9.00	356.62
涂刷防水涂料2遍	17.05	28.6	21.2	2.13	54.53	5.00	9.00	1,013.42
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	17.05	28.6	21.2	2.13	54.53	5.00	9.00	1,013.42
涂刷界面剂	18.6	4.77	7.65	1.26	14.36	5.00	9.00	291.14
德高界面处理剂	18.6	4.77	7.65	1.26	14.36	5.00	9.00	291.14
外墙涂料	17.9	8.56	12.16	1.97	23.82	5.00	9.00	464.75
外墙溶剂涂料一底二面	17.9	8.56	12.16	1.97	23.82	5.00	9.00	464.75
130-2401北阳台北外墙	85.18	364.21	391.87	402.61	1,216.62	5.00	9.00	3,324.65
表面清理	14.6	15.56		2.43	18.89	5.00	9.00	300.61
对原墙面落灰、起皮的地方进行铲除	14.6	15.56		2.43	18.89	5.00	9.00	300.61
窗口打胶	0	95.17	190.21	12.41	312.68	5.00	9.00	0.00
窗口原密封胶铲除，重新打硅宝结构耐候胶	0	95.17	190.21	12.41	312.68	5.00	9.00	0.00
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.38	12	15	4	32.55	5.00	9.00	155.40
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	4.38	12	15	4	32.55	5.00	9.00	155.40
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	95.43
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	8.76	20.66	10.51	2.33	35.18	5.00	9.00	335.92
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	8.76	20.66	10.51	2.33	35.18	5.00	9.00	335.92
涂刷防水涂料2遍	16.06	28.6	21.2	2.13	54.53	5.00	9.00	954.57
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	16.06	28.6	21.2	2.13	54.53	5.00	9.00	954.57
涂刷界面剂	17.52	4.77	7.65	1.26	14.36	5.00	9.00	274.23
德高界面处理剂	17.52	4.77	7.65	1.26	14.36	5.00	9.00	274.23
外墙涂料	16.86	8.56	12.16	1.97	23.82	5.00	9.00	437.75
外墙溶剂涂料一底二面	16.86	8.56	12.16	1.97	23.82	5.00	9.00	437.75
130-2401南阳台南外墙	99.04	364.21	391.87	402.61	1,216.62	5.00	9.00	4,100.56
表面清理	16.2	15.56		2.43	18.89	5.00	9.00	333.56
对原墙面落灰、起皮的地方进行铲除	16.2	15.56		2.43	18.89	5.00	9.00	333.56
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.86	12	15	4	32.55	5.00	9.00	172.43
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	4.86	12	15	4	32.55	5.00	9.00	172.43
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	95.43
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	9.72	20.66	10.51	2.33	35.18	5.00	9.00	372.73
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	9.72	20.66	10.51	2.33	35.18	5.00	9.00	372.73
涂刷防水涂料2遍	19.44	28.6	21.2	2.13	54.53	5.00	9.00	1,155.47
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	19.44	28.6	21.2	2.13	54.53	5.00	9.00	1,155.47
涂刷界面剂	19.44	4.77	7.65	1.26	14.36	5.00	9.00	304.28
德高界面处理剂	19.44	4.77	7.65	1.26	14.36	5.00	9.00	304.28

外墙涂料	21.38	8.56	12.16	1.97	23.82	5.00	9.00	555.10
外墙溶剂涂料一底二面	21.38	8.56	12.16	1.97	23.82	5.00	9.00	555.10
130-2401南阳台东侧漏水	111.28	364.21	391.87	402.61	1,216.62	5.00	9.00	4,442.39
表面清理	19.1	15.56		2.43	18.89	5.00	9.00	393.27
对原墙面落灰、起皮的地方进行铲除	19.1	15.56		2.43	18.89	5.00	9.00	393.27
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.73	12	15	4	32.55	5.00	9.00	203.30
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.73	12	15	4	32.55	5.00	9.00	203.30
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	11.46	20.66	10.51	2.33	35.18	5.00	9.00	439.44
采用3mm立邦抗裂防水砂浆，对墙面进行找平	11.46	20.66	10.51	2.33	35.18	5.00	9.00	439.44
涂刷防水涂料2遍	21.01	28.6	21.2	2.13	54.53	5.00	9.00	1,248.79
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.01	28.6	21.2	2.13	54.53	5.00	9.00	1,248.79
涂刷界面剂	22.92	4.77	7.65	1.26	14.36	5.00	9.00	358.75
德高界面处理剂	22.92	4.77	7.65	1.26	14.36	5.00	9.00	358.75
外墙涂料	22.06	8.56	12.16	1.97	23.82	5.00	9.00	572.76
外墙溶剂涂料一底二面	22.06	8.56	12.16	1.97	23.82	5.00	9.00	572.76
130-2501北客厅北外墙漏水	102.11	364.21	391.87	402.61	1,216.62	5.00	9.00	4,463.40
表面清理	17.2	15.56		2.43	18.89	5.00	9.00	354.15
对原墙面落灰、起皮的地方进行铲除	17.2	15.56		2.43	18.89	5.00	9.00	354.15
窗口打胶	2	95.17	190.21	12.41	312.68	5.00	9.00	681.64
窗口原密封胶铲除，重新打硅宝结构耐候胶	2	95.17	190.21	12.41	312.68	5.00	9.00	681.64
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.16	12	15	4	32.55	5.00	9.00	183.08
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.16	12	15	4	32.55	5.00	9.00	183.08
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	10.32	20.66	10.51	2.33	35.18	5.00	9.00	395.74
采用3mm立邦抗裂防水砂浆，对墙面进行找平	10.32	20.66	10.51	2.33	35.18	5.00	9.00	395.74
涂刷防水涂料2遍	18.92	28.6	21.2	2.13	54.53	5.00	9.00	1,124.56
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	18.92	28.6	21.2	2.13	54.53	5.00	9.00	1,124.56
涂刷界面剂	20.64	4.77	7.65	1.26	14.36	5.00	9.00	323.07
德高界面处理剂	20.64	4.77	7.65	1.26	14.36	5.00	9.00	323.07
外墙涂料	19.87	8.56	12.16	1.97	23.82	5.00	9.00	515.90
外墙溶剂涂料一底二面	19.87	8.56	12.16	1.97	23.82	5.00	9.00	515.90
130-2501北卧室北外墙漏水	95.82	364.21	391.87	402.61	1,216.62	5.00	9.00	3,968.59
表面清理	16.4	15.56		2.43	18.89	5.00	9.00	337.68
对原墙面落灰、起皮的地方进行铲除	16.4	15.56		2.43	18.89	5.00	9.00	337.68
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.92	12	15	4	32.55	5.00	9.00	174.56
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	4.92	12	15	4	32.55	5.00	9.00	174.56
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	9.84	20.66	10.51	2.33	35.18	5.00	9.00	377.33
采用3mm立邦抗裂防水砂浆，对墙面进行找平	9.84	20.66	10.51	2.33	35.18	5.00	9.00	377.33
涂刷防水涂料2遍	18.04	28.6	21.2	2.13	54.53	5.00	9.00	1,072.25
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	18.04	28.6	21.2	2.13	54.53	5.00	9.00	1,072.25
涂刷界面剂	19.68	4.77	7.65	1.26	14.36	5.00	9.00	308.03
德高界面处理剂	19.68	4.77	7.65	1.26	14.36	5.00	9.00	308.03
外墙涂料	18.94	8.56	12.16	1.97	23.82	5.00	9.00	491.75
外墙溶剂涂料一底二面	18.94	8.56	12.16	1.97	23.82	5.00	9.00	491.75
130-2501南主卧南外墙漏水	111.82	364.21	391.87	402.61	1,216.62	5.00	9.00	4,459.34
表面清理	19.2	15.56		2.43	18.89	5.00	9.00	395.33
对原墙面落灰、起皮的地方进行铲除	19.2	15.56		2.43	18.89	5.00	9.00	395.33
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.76	12	15	4	32.55	5.00	9.00	204.36
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.76	12	15	4	32.55	5.00	9.00	204.36
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	11.52	20.66	10.51	2.33	35.18	5.00	9.00	441.74
采用3mm立邦抗裂防水砂浆，对墙面进行找平	11.52	20.66	10.51	2.33	35.18	5.00	9.00	441.74



涂刷防水涂料2遍	21.12	28.6	21.2	2.13	54.53	5.00	9.00	1,255.32
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.12	28.6	21.2	2.13	54.53	5.00	9.00	1,255.32
涂刷界面剂	23.04	4.77	7.65	1.26	14.36	5.00	9.00	360.63
德高界面处理剂	23.04	4.77	7.65	1.26	14.36	5.00	9.00	360.63
外墙涂料	22.18	8.56	12.16	1.97	23.82	5.00	9.00	575.88
外墙溶剂涂料一底二面	22.18	8.56	12.16	1.97	23.82	5.00	9.00	575.88
130-2502厨房南主卧外墙	66.98	364.21	391.87	402.61	1,216.62	5.00	9.00	3,074.02
表面清理	11.2	15.56		2.43	18.89	5.00	9.00	230.61
对原墙面落灰、起皮的地方进行铲除	11.2	15.56		2.43	18.89	5.00	9.00	230.61
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	3.36	12	15	4	32.55	5.00	9.00	119.21
对窗台与外墙面接缝处，原密封胶铲除，重新打	3.36	12	15	4	32.55	5.00	9.00	119.21
垃圾清理	4	13.16		3.52	17.51	5.00	9.00	76.34
人工清理建筑垃圾并装袋，垂直运输短驳	4	13.16		3.52	17.51	5.00	9.00	76.34
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	6.72	20.66	10.51	2.33	35.18	5.00	9.00	257.69
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	6.72	20.66	10.51	2.33	35.18	5.00	9.00	257.69
涂刷防水涂料2遍	12.32	28.6	21.2	2.13	54.53	5.00	9.00	732.27
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	12.32	28.6	21.2	2.13	54.53	5.00	9.00	732.27
涂刷界面剂	13.44	4.77	7.65	1.26	14.36	5.00	9.00	210.37
德高界面处理剂	13.44	4.77	7.65	1.26	14.36	5.00	9.00	210.37
外墙涂料	12.94	8.56	12.16	1.97	23.82	5.00	9.00	335.97
外墙溶剂涂料一底二面	12.94	8.56	12.16	1.97	23.82	5.00	9.00	335.97
130-2702南阳台外墙漏水	126.74	364.21	391.87	402.61	1,216.62	5.00	9.00	4,916.18
表面清理	21.8	15.56		2.43	18.89	5.00	9.00	448.86
对原墙面落灰、起皮的地方进行铲除	21.8	15.56		2.43	18.89	5.00	9.00	448.86
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	6.54	12	15	4	32.55	5.00	9.00	232.04
对窗台与外墙面接缝处，原密封胶铲除，重新打	6.54	12	15	4	32.55	5.00	9.00	232.04
垃圾清理	7	13.16		3.52	17.51	5.00	9.00	133.60
人工清理建筑垃圾并装袋，垂直运输短驳	7	13.16		3.52	17.51	5.00	9.00	133.60
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	13.08	20.66	10.51	2.33	35.18	5.00	9.00	501.56
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	13.08	20.66	10.51	2.33	35.18	5.00	9.00	501.56
涂刷防水涂料2遍	23.98	28.6	21.2	2.13	54.53	5.00	9.00	1,425.32
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	23.98	28.6	21.2	2.13	54.53	5.00	9.00	1,425.32
涂刷界面剂	26.16	4.77	7.65	1.26	14.36	5.00	9.00	409.47
德高界面处理剂	26.16	4.77	7.65	1.26	14.36	5.00	9.00	409.47
外墙涂料	25.18	8.56	12.16	1.97	23.82	5.00	9.00	653.77
外墙溶剂涂料一底二面	25.18	8.56	12.16	1.97	23.82	5.00	9.00	653.77
130-2703南主卧室南外墙漏水	111.82	364.21	391.87	402.61	1,216.62	5.00	9.00	4,459.34
表面清理	19.2	15.56		2.43	18.89	5.00	9.00	395.33
对原墙面落灰、起皮的地方进行铲除	19.2	15.56		2.43	18.89	5.00	9.00	395.33
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.76	12	15	4	32.55	5.00	9.00	204.36
对窗台与外墙面接缝处，原密封胶铲除，重新打	5.76	12	15	4	32.55	5.00	9.00	204.36
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	11.52	20.66	10.51	2.33	35.18	5.00	9.00	441.74
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	11.52	20.66	10.51	2.33	35.18	5.00	9.00	441.74
涂刷防水涂料2遍	21.12	28.6	21.2	2.13	54.53	5.00	9.00	1,255.32
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.12	28.6	21.2	2.13	54.53	5.00	9.00	1,255.32
涂刷界面剂	23.04	4.77	7.65	1.26	14.36	5.00	9.00	360.63
德高界面处理剂	23.04	4.77	7.65	1.26	14.36	5.00	9.00	360.63
外墙涂料	22.18	8.56	12.16	1.97	23.82	5.00	9.00	575.88
外墙溶剂涂料一底二面	22.18	8.56	12.16	1.97	23.82	5.00	9.00	575.88
130-2801北客厅北外墙漏水东侧	95.29	364.21	391.87	402.61	1,216.62	5.00	9.00	3,951.91
表面清理	16.3	15.56		2.43	18.89	5.00	9.00	335.62
对原墙面落灰、起皮的地方进行铲除	16.3	15.56		2.43	18.89	5.00	9.00	335.62
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.89	12	15	4	32.55	5.00	9.00	173.50
对窗台与外墙面接缝处，原密封胶铲除，重新打	4.89	12	15	4	32.55	5.00	9.00	173.50
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	95.43


垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	9.78	20.66	10.51	2.33	35.18	5.00	9.00	375.03
采用3mm立邦抗裂防水砂浆，对墙面进行找平	9.78	20.66	10.51	2.33	35.18	5.00	9.00	375.03
涂刷防水涂料2遍	17.93	28.6	21.2	2.13	54.53	5.00	9.00	1,065.71
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	17.93	28.6	21.2	2.13	54.53	5.00	9.00	1,065.71
涂刷界面剂	19.56	4.77	7.65	1.26	14.36	5.00	9.00	306.16
德高界面处理剂	19.56	4.77	7.65	1.26	14.36	5.00	9.00	306.16
外墙涂料	18.83	8.56	12.16	1.97	23.82	5.00	9.00	488.90
外墙溶剂涂料一底二面	18.83	8.56	12.16	1.97	23.82	5.00	9.00	488.90
130-2801南主卧南外墙	112.35	364.21	391.87	402.61	1,216.62	5.00	9.00	4,476.04
表面清理	19.3	15.56		2.43	18.89	5.00	9.00	397.39
对原墙面落灰、起皮的地方进行铲除	19.3	15.56		2.43	18.89	5.00	9.00	397.39
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.79	12	15	4	32.55	5.00	9.00	205.42
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.79	12	15	4	32.55	5.00	9.00	205.42
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	11.58	20.66	10.51	2.33	35.18	5.00	9.00	444.04
采用3mm立邦抗裂防水砂浆，对墙面进行找平	11.58	20.66	10.51	2.33	35.18	5.00	9.00	444.04
涂刷防水涂料2遍	21.23	28.6	21.2	2.13	54.53	5.00	9.00	1,261.86
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.23	28.6	21.2	2.13	54.53	5.00	9.00	1,261.86
涂刷界面剂	23.16	4.77	7.65	1.26	14.36	5.00	9.00	362.51
德高界面处理剂	23.16	4.77	7.65	1.26	14.36	5.00	9.00	362.51
外墙涂料	22.29	8.56	12.16	1.97	23.82	5.00	9.00	578.74
外墙溶剂涂料一底二面	22.29	8.56	12.16	1.97	23.82	5.00	9.00	578.74
130-3001北客厅阳台北外墙漏水	94.75	364.21	391.87	402.61	1,216.62	5.00	9.00	3,934.94
表面清理	16.2	15.56		2.43	18.89	5.00	9.00	333.56
对原墙面落灰、起皮的地方进行铲除	16.2	15.56		2.43	18.89	5.00	9.00	333.56
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.86	12	15	4	32.55	5.00	9.00	172.43
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	4.86	12	15	4	32.55	5.00	9.00	172.43
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	95.43
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	9.72	20.66	10.51	2.33	35.18	5.00	9.00	372.73
采用3mm立邦抗裂防水砂浆，对墙面进行找平	9.72	20.66	10.51	2.33	35.18	5.00	9.00	372.73
涂刷防水涂料2遍	17.82	28.6	21.2	2.13	54.53	5.00	9.00	1,059.17
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	17.82	28.6	21.2	2.13	54.53	5.00	9.00	1,059.17
涂刷界面剂	19.44	4.77	7.65	1.26	14.36	5.00	9.00	304.28
德高界面处理剂	19.44	4.77	7.65	1.26	14.36	5.00	9.00	304.28
外墙涂料	18.71	8.56	12.16	1.97	23.82	5.00	9.00	485.78
外墙溶剂涂料一底二面	18.71	8.56	12.16	1.97	23.82	5.00	9.00	485.78
130-301北次卧北外墙漏水	80.29	364.21	391.87	402.61	1,216.62	5.00	9.00	3,480.25
表面清理	13.5	15.56		2.43	18.89	5.00	9.00	277.99
对原墙面落灰、起皮的地方进行铲除	13.5	15.56		2.43	18.89	5.00	9.00	277.99
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.05	12	15	4	32.55	5.00	9.00	143.69
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	4.05	12	15	4	32.55	5.00	9.00	143.69
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	95.43
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	8.1	20.66	10.51	2.33	35.18	5.00	9.00	310.61
采用3mm立邦抗裂防水砂浆，对墙面进行找平	8.1	20.66	10.51	2.33	35.18	5.00	9.00	310.61
涂刷防水涂料2遍	14.85	28.6	21.2	2.13	54.53	5.00	9.00	882.65
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	14.85	28.6	21.2	2.13	54.53	5.00	9.00	882.65
涂刷界面剂	16.2	4.77	7.65	1.26	14.36	5.00	9.00	253.57
德高界面处理剂	16.2	4.77	7.65	1.26	14.36	5.00	9.00	253.57
外墙涂料	15.59	8.56	12.16	1.97	23.82	5.00	9.00	404.77
外墙溶剂涂料一底二面	15.59	8.56	12.16	1.97	23.82	5.00	9.00	404.77
130-301北卧室北外墙漏水	87.25	364.21	391.87	402.61	1,216.62	5.00	9.00	3,699.12
表面清理	14.8	15.56		2.43	18.89	5.00	9.00	304.73
对原墙面落灰、起皮的地方进行铲除	14.8	15.56		2.43	18.89	5.00	9.00	304.73
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49

接缝处打胶	4.44	12	15	4	32.55	5.00	9.00	157.53
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	4.44	12	15	4	32.55	5.00	9.00	157.53
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	95.43
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	8.88	20.66	10.51	2.33	35.18	5.00	9.00	340.52
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	8.88	20.66	10.51	2.33	35.18	5.00	9.00	340.52
涂刷防水涂料2遍	16.28	28.6	21.2	2.13	54.53	5.00	9.00	967.65
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	16.28	28.6	21.2	2.13	54.53	5.00	9.00	967.65
涂刷界面剂	17.76	4.77	7.65	1.26	14.36	5.00	9.00	277.98
德高界面处理剂	17.76	4.77	7.65	1.26	14.36	5.00	9.00	277.98
外墙涂料	17.09	8.56	12.16	1.97	23.82	5.00	9.00	443.72
外墙溶剂涂料一底二面	17.09	8.56	12.16	1.97	23.82	5.00	9.00	443.72
130-301北杂物间北外墙漏水	84.58	364.21	391.87	402.61	1,216.62	5.00	9.00	3,615.14
表面清理	14.3	15.56		2.43	18.89	5.00	9.00	294.44
对原墙面落灰、起皮的地方进行铲除	14.3	15.56		2.43	18.89	5.00	9.00	294.44
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.29	12	15	4	32.55	5.00	9.00	152.21
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	4.29	12	15	4	32.55	5.00	9.00	152.21
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	95.43
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	8.58	20.66	10.51	2.33	35.18	5.00	9.00	329.01
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	8.58	20.66	10.51	2.33	35.18	5.00	9.00	329.01
涂刷防水涂料2遍	15.73	28.6	21.2	2.13	54.53	5.00	9.00	934.96
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	15.73	28.6	21.2	2.13	54.53	5.00	9.00	934.96
涂刷界面剂	17.16	4.77	7.65	1.26	14.36	5.00	9.00	268.60
德高界面处理剂	17.16	4.77	7.65	1.26	14.36	5.00	9.00	268.60
外墙涂料	16.52	8.56	12.16	1.97	23.82	5.00	9.00	428.93
外墙溶剂涂料一底二面	16.52	8.56	12.16	1.97	23.82	5.00	9.00	428.93
130-301客厅南阳台漏水	92.07	364.21	391.87	402.61	1,216.62	5.00	9.00	3,850.70
表面清理	15.7	15.56		2.43	18.89	5.00	9.00	323.26
对原墙面落灰、起皮的地方进行铲除	15.7	15.56		2.43	18.89	5.00	9.00	323.26
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	4.71	12	15	4	32.55	5.00	9.00	167.11
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	4.71	12	15	4	32.55	5.00	9.00	167.11
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	95.43
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	9.42	20.66	10.51	2.33	35.18	5.00	9.00	361.23
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	9.42	20.66	10.51	2.33	35.18	5.00	9.00	361.23
涂刷防水涂料2遍	17.27	28.6	21.2	2.13	54.53	5.00	9.00	1,026.49
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	17.27	28.6	21.2	2.13	54.53	5.00	9.00	1,026.49
涂刷界面剂	18.84	4.77	7.65	1.26	14.36	5.00	9.00	294.59
德高界面处理剂	18.84	4.77	7.65	1.26	14.36	5.00	9.00	294.59
外墙涂料	18.13	8.56	12.16	1.97	23.82	5.00	9.00	470.73
外墙溶剂涂料一底二面	18.13	8.56	12.16	1.97	23.82	5.00	9.00	470.73
130-301南卧室南外墙漏水	115.42	364.21	391.87	402.61	1,216.62	5.00	9.00	6,830.29
表面清理	19.5	15.56		2.43	18.89	5.00	9.00	401.51
对原墙面落灰、起皮的地方进行铲除	19.5	15.56		2.43	18.89	5.00	9.00	401.51
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	2	115.73	135.14	12.56	276.60	5.00	9.00	602.99
采用YH东方雨虹对缝隙堵漏	2	115.73	135.14	12.56	276.60	5.00	9.00	602.99
接缝处打胶	5.85	12	15	4	32.55	5.00	9.00	207.56
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.85	12	15	4	32.55	5.00	9.00	207.56
垃圾清理	7	13.16		3.52	17.51	5.00	9.00	133.60
人工清理建筑垃圾并装袋，垂直运输短驳	7	13.16		3.52	17.51	5.00	9.00	133.60
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	11.7	20.66	10.51	2.33	35.18	5.00	9.00	448.65
采用3mm立邦抗裂耐水砂浆，对墙面进行找平	11.7	20.66	10.51	2.33	35.18	5.00	9.00	448.65
涂刷防水涂料2遍	21.45	28.6	21.2	2.13	54.53	5.00	9.00	1,274.94
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.45	28.6	21.2	2.13	54.53	5.00	9.00	1,274.94
涂刷界面剂	23.4	4.77	7.65	1.26	14.36	5.00	9.00	366.26
德高界面处理剂	23.4	4.77	7.65	1.26	14.36	5.00	9.00	366.26
外墙涂料	22.52	8.56	12.16	1.97	23.82	5.00	9.00	584.71
外墙溶剂涂料一底二面	22.52	8.56	12.16	1.97	23.82	5.00	9.00	584.71
130-303客厅南阳台外墙漏水	128.81	364.21	391.87	402.61	1,216.62	5.00	9.00	5,290.65
表面清理	22	15.56		2.43	18.89	5.00	9.00	452.98
对原墙面落灰、起皮的地方进行铲除	22	15.56		2.43	18.89	5.00	9.00	452.98

窗口打胶	2	95.17	190.21	12.41	312.68	5.00	9.00	681.64
窗口原密封胶铲除，重新打硅宝结构耐候胶	2	95.17	190.21	12.41	312.68	5.00	9.00	681.64
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	6.6	12	15	4	32.55	5.00	9.00	234.16
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	6.6	12	15	4	32.55	5.00	9.00	234.16
垃圾清理	7	13.16		3.52	17.51	5.00	9.00	133.60
人工清理建筑垃圾并装袋，垂直运输短驳	7	13.16		3.52	17.51	5.00	9.00	133.60
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	13.2	20.66	10.51	2.33	35.18	5.00	9.00	506.17
采用3mm立邦抗裂防水砂浆，对墙面进行找平	13.2	20.66	10.51	2.33	35.18	5.00	9.00	506.17
涂刷防水涂料2遍	24.2	28.6	21.2	2.13	54.53	5.00	9.00	1,438.40
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	24.2	28.6	21.2	2.13	54.53	5.00	9.00	1,438.40
涂刷界面剂	26.4	4.77	7.65	1.26	14.36	5.00	9.00	413.22
德高界面处理剂	26.4	4.77	7.65	1.26	14.36	5.00	9.00	413.22
外墙涂料	25.41	8.56	12.16	1.97	23.82	5.00	9.00	659.74
外墙溶剂涂料一底二面	25.41	8.56	12.16	1.97	23.82	5.00	9.00	659.74
130-303南卧室南外墙漏水	111.82	364.21	391.87	402.61	1,216.62	5.00	9.00	4,459.34
表面清理	19.2	15.56		2.43	18.89	5.00	9.00	395.33
对原墙面落灰、起皮的地方进行铲除	19.2	15.56		2.43	18.89	5.00	9.00	395.33
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.76	12	15	4	32.55	5.00	9.00	204.36
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.76	12	15	4	32.55	5.00	9.00	204.36
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	11.52	20.66	10.51	2.33	35.18	5.00	9.00	441.74
采用3mm立邦抗裂防水砂浆，对墙面进行找平	11.52	20.66	10.51	2.33	35.18	5.00	9.00	441.74
涂刷防水涂料2遍	21.12	28.6	21.2	2.13	54.53	5.00	9.00	1,255.32
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.12	28.6	21.2	2.13	54.53	5.00	9.00	1,255.32
涂刷界面剂	23.04	4.77	7.65	1.26	14.36	5.00	9.00	360.63
德高界面处理剂	23.04	4.77	7.65	1.26	14.36	5.00	9.00	360.63
外墙涂料	22.18	8.56	12.16	1.97	23.82	5.00	9.00	575.88
外墙溶剂涂料一底二面	22.18	8.56	12.16	1.97	23.82	5.00	9.00	575.88
130-3103客厅南阳台外墙漏水	107.46	364.21	391.87	402.61	1,216.62	5.00	9.00	4,592.33
表面清理	18.2	15.56		2.43	18.89	5.00	9.00	374.74
对原墙面落灰、起皮的地方进行铲除	18.2	15.56		2.43	18.89	5.00	9.00	374.74
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	2	115.73	135.14	12.56	276.60	5.00	9.00	602.99
采用YH东方雨虹对缝隙堵漏	2	115.73	135.14	12.56	276.60	5.00	9.00	602.99
接缝处打胶	5.46	12	15	4	32.55	5.00	9.00	193.71
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.46	12	15	4	32.55	5.00	9.00	193.71
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	10.92	20.66	10.51	2.33	35.18	5.00	9.00	418.75
采用3mm立邦抗裂防水砂浆，对墙面进行找平	10.92	20.66	10.51	2.33	35.18	5.00	9.00	418.75
涂刷防水涂料2遍	20.02	28.6	21.2	2.13	54.53	5.00	9.00	1,189.94
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	20.02	28.6	21.2	2.13	54.53	5.00	9.00	1,189.94
涂刷界面剂	21.84	4.77	7.65	1.26	14.36	5.00	9.00	341.85
德高界面处理剂	21.84	4.77	7.65	1.26	14.36	5.00	9.00	341.85
外墙涂料	21.02	8.56	12.16	1.97	23.82	5.00	9.00	545.76
外墙溶剂涂料一底二面	21.02	8.56	12.16	1.97	23.82	5.00	9.00	545.76
130-401南阳台外墙漏水	109.6	364.21	391.87	402.61	1,216.62	5.00	9.00	4,698.95
表面清理	18.6	15.56		2.43	18.89	5.00	9.00	382.97
对原墙面落灰、起皮的地方进行铲除	18.6	15.56		2.43	18.89	5.00	9.00	382.97
窗口打胶	2	95.17	190.21	12.41	312.68	5.00	9.00	681.64
窗口原密封胶铲除，重新打硅宝结构耐候胶	2	95.17	190.21	12.41	312.68	5.00	9.00	681.64
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.58	12	15	4	32.55	5.00	9.00	197.98
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.58	12	15	4	32.55	5.00	9.00	197.98
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	11.16	20.66	10.51	2.33	35.18	5.00	9.00	427.94
采用3mm立邦抗裂防水砂浆，对墙面进行找平	11.16	20.66	10.51	2.33	35.18	5.00	9.00	427.94
涂刷防水涂料2遍	20.46	28.6	21.2	2.13	54.53	5.00	9.00	1,216.09
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	20.46	28.6	21.2	2.13	54.53	5.00	9.00	1,216.09
涂刷界面剂	22.32	4.77	7.65	1.26	14.36	5.00	9.00	349.37
德高界面处理剂	22.32	4.77	7.65	1.26	14.36	5.00	9.00	349.37
外墙涂料	21.48	8.56	12.16	1.97	23.82	5.00	9.00	557.70

外墙溶剂涂料一底二面	21.48	8.56	12.16	1.97	23.82	5.00	9.00	557.70
130-4楼电梯窗户外墙	26.14	321.43	411.83	414.93	1,205.59	5.00	9.00	2,664.31
打胶	8	12	15	4	32.55	5.00	9.00	283.84
打硅宝结构耐候胶	8	12	15	4	32.55	5.00	9.00	283.84
大理石安装	2	7.86	355	2.15	383.26	5.00	9.00	835.51
定制大理石吊运并安装	2	7.86	355	2.15	383.26	5.00	9.00	835.51
高空清理垃圾	4	28.71	0.82	7.66	39.05	5.00	9.00	170.26
蜘蛛人工清理高空建筑垃圾至平台，二次清理装袋	4	28.71	0.82	7.66	39.05	5.00	9.00	170.26
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
平台大理石拆除	2.5	180.93	0	35.76	227.52	5.00	9.00	619.99
蜘蛛人高空对原外立面石膏板进行破碎拆除	2.5	180.93	0	35.76	227.52	5.00	9.00	619.99
涂刷防水涂料2遍	2.75	28.6	21.2	2.13	54.53	5.00	9.00	163.46
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	2.75	28.6	21.2	2.13	54.53	5.00	9.00	163.46
涂刷界面剂	3	4.77	7.65	1.26	14.36	5.00	9.00	46.96
德高界面处理剂	3	4.77	7.65	1.26	14.36	5.00	9.00	46.96
外墙涂料	2.89	8.56	12.16	1.97	23.82	5.00	9.00	75.04
外墙溶剂涂料一底二面	2.89	8.56	12.16	1.97	23.82	5.00	9.00	75.04
130-802主卧东侧外墙漏水	119.31	364.21	391.87	402.61	1,216.62	5.00	9.00	4,373.17
表面清理	20.6	15.56		2.43	18.89	5.00	9.00	424.15
对原墙面落灰、起皮的地方进行铲除	20.6	15.56		2.43	18.89	5.00	9.00	424.15
窗口打胶	0	95.17	190.21	12.41	312.68	5.00	9.00	0.00
窗口原密封胶铲除，重新打硅宝结构耐候胶	0	95.17	190.21	12.41	312.68	5.00	9.00	0.00
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	6.18	12	15	4	32.55	5.00	9.00	219.26
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	6.18	12	15	4	32.55	5.00	9.00	219.26
垃圾清理	7	13.16		3.52	17.51	5.00	9.00	133.60
人工清理建筑垃圾并装袋，垂直运输短驳	7	13.16		3.52	17.51	5.00	9.00	133.60
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	12.36	20.66	10.51	2.33	35.18	5.00	9.00	473.95
采用3mm立邦抗裂防水砂浆，对墙面进行找平	12.36	20.66	10.51	2.33	35.18	5.00	9.00	473.95
涂刷防水涂料2遍	22.66	28.6	21.2	2.13	54.53	5.00	9.00	1,346.86
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	22.66	28.6	21.2	2.13	54.53	5.00	9.00	1,346.86
涂刷界面剂	24.72	4.77	7.65	1.26	14.36	5.00	9.00	386.93
德高界面处理剂	24.72	4.77	7.65	1.26	14.36	5.00	9.00	386.93
外墙涂料	23.79	8.56	12.16	1.97	23.82	5.00	9.00	617.68
外墙溶剂涂料一底二面	23.79	8.56	12.16	1.97	23.82	5.00	9.00	617.68
130-901南客厅阳台外墙漏水	171.97	364.21	391.87	402.61	1,216.62	5.00	9.00	6,610.82
表面清理	29.5	15.56		2.43	18.89	5.00	9.00	607.41
对原墙面落灰、起皮的地方进行铲除	29.5	15.56		2.43	18.89	5.00	9.00	607.41
窗口打胶	2	95.17	190.21	12.41	312.68	5.00	9.00	681.64
窗口原密封胶铲除，重新打硅宝结构耐候胶	2	95.17	190.21	12.41	312.68	5.00	9.00	681.64
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	8.85	12	15	4	32.55	5.00	9.00	314.00
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	8.85	12	15	4	32.55	5.00	9.00	314.00
垃圾清理	10	13.16		3.52	17.51	5.00	9.00	190.86
人工清理建筑垃圾并装袋，垂直运输短驳	10	13.16		3.52	17.51	5.00	9.00	190.86
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	17.7	20.66	10.51	2.33	35.18	5.00	9.00	678.73
采用3mm立邦抗裂防水砂浆，对墙面进行找平	17.7	20.66	10.51	2.33	35.18	5.00	9.00	678.73
涂刷防水涂料2遍	32.45	28.6	21.2	2.13	54.53	5.00	9.00	1,428.46
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	32.45	28.6	21.2	2.13	54.53	5.00	9.00	1,428.46
涂刷界面剂	35.4	4.77	7.65	1.26	14.36	5.00	9.00	855.99
德高界面处理剂	35.4	4.77	7.65	1.26	14.36	5.00	9.00	855.99
外墙涂料	34.07	8.56	12.16	1.97	23.82	5.00	9.00	884.59
外墙溶剂涂料一底二面	34.07	8.56	12.16	1.97	23.82	5.00	9.00	884.59
130-901南主卧外墙漏水	118.71	364.21	391.87	402.61	1,216.62	5.00	9.00	4,664.64
表面清理	20.3	15.56		2.43	18.89	5.00	9.00	417.98
对原墙面落灰、起皮的地方进行铲除	20.3	15.56		2.43	18.89	5.00	9.00	417.98
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	6.09	12	15	4	32.55	5.00	9.00	216.07
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	6.09	12	15	4	32.55	5.00	9.00	216.07
垃圾清理	7	13.16		3.52	17.51	5.00	9.00	133.60
人工清理建筑垃圾并装袋，垂直运输短驳	7	13.16		3.52	17.51	5.00	9.00	133.60
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
砂浆抹面找平	12.18	20.66	10.51	2.33	35.18	5.00	9.00	467.05
采用3mm立邦抗裂防水砂浆，对墙面进行找平	12.18	20.66	10.51	2.33	35.18	5.00	9.00	467.05
涂刷防水涂料2遍	22.33	28.6	21.2	2.13	54.53	5.00	9.00	1,327.24
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	22.33	28.6	21.2	2.13	54.53	5.00	9.00	1,327.24
涂刷界面剂	24.36	4.77	7.65	1.26	14.36	5.00	9.00	381.29
德高界面处理剂	24.36	4.77	7.65	1.26	14.36	5.00	9.00	381.29
外墙涂料	23.45	8.56	12.16	1.97	23.82	5.00	9.00	608.85

外墙溶剂涂料一底二面	23.45	8.56	12.16	1.97	23.82	5.00	9.00	608.85
130顶楼北侧外墙排险修复	613.96	388.97	59.45	423.92	915.95	5.00	9.00	29,096.95
钢筋切除	130	7.86		2.15	10.51	5.00	9.00	1,489.27
采用砂轮锯对外露钢筋进行切除	130	7.86		2.15	10.51	5.00	9.00	1,489.27
高空清理垃圾	65	28.71	0.82	7.66	39.05	5.00	9.00	2,766.69
蜘蛛人工清理高空建筑垃圾至平台，二次清理装袋	65	28.71	0.82	7.66	39.05	5.00	9.00	2,766.69
基础处理	71.28	7.56	0	2.43	10.49	5.00	9.00	815.03
对现状U型面进行清理找平	71.28	7.56	0	2.43	10.49	5.00	9.00	815.03
垃圾外运	6	50		360	430.50	5.00	9.00	2,815.47
自卸汽车运土（8t以内）（运距25km以内）	6	50		360	430.50	5.00	9.00	2,815.47
涂刷防水涂料2遍	78.41	28.6	21.2	2.13	54.53	5.00	9.00	4,660.51
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	78.41	28.6	21.2	2.13	54.53	5.00	9.00	4,660.51
涂刷界面剂	71.28	4.77	7.65	1.26	14.36	5.00	9.00	1,115.70
德高界面处理剂	71.28	4.77	7.65	1.26	14.36	5.00	9.00	1,115.70
外立面石膏板切割	64.8	55.56		8.43	67.19	5.00	9.00	4,745.76
蜘蛛人高空采用砂轮锯对原外立面石膏板切割	64.8	55.56		8.43	67.19	5.00	9.00	4,745.76
外墙涂料	82.33	8.56	12.16	1.97	23.82	5.00	9.00	2,137.60
外墙溶剂涂料一底二面	82.33	8.56	12.16	1.97	23.82	5.00	9.00	2,137.60
原外立面排险拆除	32.4	180.93	0	35.76	227.52	5.00	9.00	8,035.10
蜘蛛人高空对原外立面石膏板进行破碎拆除	32.4	180.93	0	35.76	227.52	5.00	9.00	8,035.10
做R角	12.46	16.42	17.62	2.13	37.98	5.00	9.00	515.82
采用3mm立邦抗裂耐水砂浆做成45°八字脚，八字	12.46	16.42	17.62	2.13	37.98	5.00	9.00	515.82
130顶楼东侧内墙排险修复	410.69	388.97	59.45	423.92	915.95	5.00	9.00	17,128.90
钢筋切除	132	7.86		2.15	10.51	5.00	9.00	1,512.18
采用砂轮锯对外露钢筋进行切除	132	7.86		2.15	10.51	5.00	9.00	1,512.18
高空清理垃圾	36	28.71	0.82	7.66	39.05	5.00	9.00	1,532.32
蜘蛛人工清理高空建筑垃圾至平台，二次清理装袋	36	28.71	0.82	7.66	39.05	5.00	9.00	1,532.32
基础处理	39.82	7.56	0	2.43	10.49	5.00	9.00	455.30
对现状U型面进行清理找平	39.82	7.56	0	2.43	10.49	5.00	9.00	455.30
垃圾外运	3	50		360	430.50	5.00	9.00	1,407.74
自卸汽车运土（8t以内）（运距25km以内）	3	50		360	430.50	5.00	9.00	1,407.74
涂刷防水涂料2遍	43.8	28.6	21.2	2.13	54.53	5.00	9.00	2,603.37
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	43.8	28.6	21.2	2.13	54.53	5.00	9.00	2,603.37
涂刷界面剂	39.82	4.77	7.65	1.26	14.36	5.00	9.00	623.28
德高界面处理剂	39.82	4.77	7.65	1.26	14.36	5.00	9.00	623.28
外立面石膏板切割	36.2	55.56		8.43	67.19	5.00	9.00	2,651.19
蜘蛛人高空采用砂轮锯对原外立面石膏板切割	36.2	55.56		8.43	67.19	5.00	9.00	2,651.19
外墙涂料	45.99	8.56	12.16	1.97	23.82	5.00	9.00	1,194.07
外墙溶剂涂料一底二面	45.99	8.56	12.16	1.97	23.82	5.00	9.00	1,194.07
原外立面排险拆除	18.1	180.93	0	35.76	227.52	5.00	9.00	4,488.74
蜘蛛人高空对原外立面石膏板进行破碎拆除	18.1	180.93	0	35.76	227.52	5.00	9.00	4,488.74
做R角	15.96	16.42	17.62	2.13	37.98	5.00	9.00	660.71
采用3mm立邦抗裂耐水砂浆做成45°八字脚，八字	15.96	16.42	17.62	2.13	37.98	5.00	9.00	660.71
130顶楼西侧外墙排险修复	1209.75	388.97	59.45	423.92	915.95	5.00	9.00	59,778.95
钢筋切除	172	7.86		2.15	10.51	5.00	9.00	1,970.41
采用砂轮锯对外露钢筋进行切除	172	7.86		2.15	10.51	5.00	9.00	1,970.41
高空清理垃圾	235	28.71	0.82	7.66	39.05	5.00	9.00	16,902.59
蜘蛛人工清理高空建筑垃圾至平台，二次清理装袋	235	28.71	0.82	7.66	39.05	5.00	9.00	16,902.59
基础处理	136.49	7.56	0	2.43	10.49	5.00	9.00	1,560.64
对现状U型面进行清理找平	136.49	7.56	0	2.43	10.49	5.00	9.00	1,560.64
垃圾外运	12	50		360	430.50	5.00	9.00	5,635.94
自卸汽车运土（8t以内）（运距25km以内）	12	50		360	430.50	5.00	9.00	5,635.94
涂刷防水涂料2遍	150.14	28.6	21.2	2.13	54.53	5.00	9.00	8,923.97
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	150.14	28.6	21.2	2.13	54.53	5.00	9.00	8,923.97
涂刷界面剂	136.49	4.77	7.65	1.26	14.36	5.00	9.00	2,136.40
德高界面处理剂	136.49	4.77	7.65	1.26	14.36	5.00	9.00	2,136.40
外立面石膏板切割	124.08	55.56		8.43	67.19	5.00	9.00	9,087.26
蜘蛛人高空采用砂轮锯对原外立面石膏板切割	124.08	55.56		8.43	67.19	5.00	9.00	9,087.26
外墙涂料	157.65	8.56	12.16	1.97	23.82	5.00	9.00	4,093.19
外墙溶剂涂料一底二面	157.65	8.56	12.16	1.97	23.82	5.00	9.00	4,093.19
原外立面排险拆除	62.04	180.93	0	35.76	227.52	5.00	9.00	15,385.72
蜘蛛人高空对原外立面石膏板进行破碎拆除	62.04	180.93	0	35.76	227.52	5.00	9.00	15,385.72
做R角	23.86	16.42	17.62	2.13	37.98	5.00	9.00	987.76
采用3mm立邦抗裂耐水砂浆做成45°八字脚，八字	23.86	16.42	17.62	2.13	37.98	5.00	9.00	987.76
130顶楼南侧外墙排险修复	423.95	388.97	59.45	423.92	915.95	5.00	9.00	19,605.23
钢筋切除	87	7.86		2.15	10.51	5.00	9.00	996.66
采用砂轮锯对外露钢筋进行切除	87	7.86		2.15	10.51	5.00	9.00	996.66
高空清理垃圾	44	28.71	0.82	7.66	39.05	5.00	9.00	1,872.84
蜘蛛人工清理高空建筑垃圾至平台，二次清理装袋	44	28.71	0.82	7.66	39.05	5.00	9.00	1,872.84
基础处理	48.07	7.56	0	2.43	10.49	5.00	9.00	549.63
对现状U型面进行清理找平	48.07	7.56	0	2.43	10.49	5.00	9.00	549.63
垃圾外运	3	50		360	430.50	5.00	9.00	1,407.74
自卸汽车运土（8t以内）（运距25km以内）	3	50		360	430.50	5.00	9.00	1,407.74
涂刷防水涂料2遍	52.88	28.6	21.2	2.13	54.53	5.00	9.00	3,143.07
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	52.88	28.6	21.2	2.13	54.53	5.00	9.00	3,143.07
涂刷界面剂	48.07	4.77	7.65	1.26	14.36	5.00	9.00	752.42
德高界面处理剂	48.07	4.77	7.65	1.26	14.36	5.00	9.00	752.42
外立面石膏板切割	43.7	55.56		8.43	67.19	5.00	9.00	3,200.46
蜘蛛人高空采用砂轮锯对原外立面石膏板切割	43.7	55.56		8.43	67.19	5.00	9.00	3,200.46
外墙涂料	55.52	8.56	12.16	1.97	23.82	5.00	9.00	1,441.51



外墙溶剂涂料一底二面	55.52	8.56	12.16	1.97	23.82	5.00	9.00	1,441.51
原外立面排险拆除	21.85	180.93	0	35.76	227.52	5.00	9.00	5,418.73
蜘蛛人高空对原外立面石膏板进行破碎拆除	21.85	180.93	0	35.76	227.52	5.00	9.00	5,418.73
做R角	19.86	16.42	17.62	2.13	37.98	5.00	9.00	822.17
采用3mm立邦抗裂耐水砂浆做成45°八字脚，八字	19.86	16.42	17.62	2.13	37.98	5.00	9.00	822.17
130顶楼西侧内墙排险修复	409.06	388.97	59.45	423.92	915.95	5.00	9.00	17,138.69
钢筋切除	132	7.86		2.15	10.51	5.00	9.00	1,512.18
采用砂轮锯对外露钢筋进行切除	132	7.86		2.15	10.51	5.00	9.00	1,512.18
高空清理垃圾	37	28.71	0.82	7.66	39.05	5.00	9.00	1,574.89
蜘蛛人工清理高空建筑垃圾至平台，二次清理装车	37	28.71	0.82	7.66	39.05	5.00	9.00	1,574.89
基础处理	40.92	7.56	0	2.43	10.49	5.00	9.00	467.88
对现状U型面进行清理找平	40.92	7.56	0	2.43	10.49	5.00	9.00	467.88
垃圾外运	3	50		360	430.50	5.00	9.00	1,407.74
自卸汽车运土（8t以内）（运距25km以内）	3	50		360	430.50	5.00	9.00	1,407.74
涂刷防水涂料2遍	45.01	28.6	21.2	2.13	54.53	5.00	9.00	2,675.30
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	45.01	28.6	21.2	2.13	54.53	5.00	9.00	2,675.30
涂刷界面剂	40.92	4.77	7.65	1.26	14.36	5.00	9.00	640.49
德高界面处理剂	40.92	4.77	7.65	1.26	14.36	5.00	9.00	640.49
外立面石膏板切割	37.2	55.56		8.43	67.19	5.00	9.00	2,724.42
蜘蛛人高空采用砂轮锯对原外立面石膏板切割	37.2	55.56		8.43	67.19	5.00	9.00	2,724.42
外墙涂料	47.26	8.56	12.16	1.97	23.82	5.00	9.00	1,227.05
外墙溶剂涂料一底二面	47.26	8.56	12.16	1.97	23.82	5.00	9.00	1,227.05
原外立面排险拆除	18.6	180.93	0	35.76	227.52	5.00	9.00	4,612.74
蜘蛛人高空对原外立面石膏板进行破碎拆除	18.6	180.93	0	35.76	227.52	5.00	9.00	4,612.74
做R角	7.15	16.42	17.62	2.13	37.98	5.00	9.00	296.00
采用3mm立邦抗裂耐水砂浆做成45°八字脚，八字	7.15	16.42	17.62	2.13	37.98	5.00	9.00	296.00
130顶楼西侧外墙排险修复	918.24	388.97	59.45	423.92	915.95	5.00	9.00	43,022.96
钢筋切除	176	7.86		2.15	10.51	5.00	9.00	2,016.24
采用砂轮锯对外露钢筋进行切除	176	7.86		2.15	10.51	5.00	9.00	2,016.24
高空清理垃圾	100	28.71	0.82	7.66	39.05	5.00	9.00	4,256.45
蜘蛛人工清理高空建筑垃圾至平台，二次清理装车	100	28.71	0.82	7.66	39.05	5.00	9.00	4,256.45
基础处理	109.82	7.56	0	2.43	10.49	5.00	9.00	1,255.69
对现状U型面进行清理找平	109.82	7.56	0	2.43	10.49	5.00	9.00	1,255.69
垃圾外运	6	50		360	430.50	5.00	9.00	2,815.47
自卸汽车运土（8t以内）（运距25km以内）	6	50		360	430.50	5.00	9.00	2,815.47
涂刷防水涂料2遍	120.8	28.6	21.2	2.13	54.53	5.00	9.00	7,180.07
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	120.8	28.6	21.2	2.13	54.53	5.00	9.00	7,180.07
涂刷界面剂	109.82	4.77	7.65	1.26	14.36	5.00	9.00	1,718.95
德高界面处理剂	109.82	4.77	7.65	1.26	14.36	5.00	9.00	1,718.95
外立面石膏板切割	99.84	55.56		8.43	67.19	5.00	9.00	7,311.99
蜘蛛人高空采用砂轮锯对原外立面石膏板切割	99.84	55.56		8.43	67.19	5.00	9.00	7,311.99
外墙涂料	126.84	8.56	12.16	1.97	23.82	5.00	9.00	3,293.25
外墙溶剂涂料一底二面	126.84	8.56	12.16	1.97	23.82	5.00	9.00	3,293.25
原外立面排险拆除	49.92	180.93	0	35.76	227.52	5.00	9.00	12,380.00
蜘蛛人高空对原外立面石膏板进行破碎拆除	49.92	180.93	0	35.76	227.52	5.00	9.00	12,380.00
做R角	19.2	16.42	17.62	2.13	37.98	5.00	9.00	794.85
采用3mm立邦抗裂耐水砂浆做成45°八字脚，八字	19.2	16.42	17.62	2.13	37.98	5.00	9.00	794.85

