




36, 37, 38	4002.06	2123.11	9579.71	610.00	16,490.05	48,855.05	1,098.00	53,252.05
36-1002客厅南阳台漏水	314.32	161.02	738.6	50.00	1,274.63	3,614.41	90.00	3,939.70
窗口打胶	95.13	65.32	12.41	5.00	181.50	363.00	9.00	395.67
窗口原密封胶铲除，重新打硅宝结构耐候胶	95.13	65.32	12.41	5.00	181.50	363.00	9.00	395.67
堵漏	97.28	45.37	8.54	5.00	168.75	317.50	9.00	346.08
采用YH东方雨虹对缝填堵	97.28	45.37	8.54	5.00	168.75	317.50	9.00	346.08
接缝处打胶	11.65	14.51	4.21	5.00	31.89	197.72	9.00	215.51
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝	11.65	14.51	4.21	5.00	31.89	197.72	9.00	215.51
垃圾清理	13.16		3.52	5.00	17.51	87.55	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	87.55	9.00	95.43
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平	14.36	8.25	2.13	5.00	25.98	241.61	9.00	263.35
采用立邦抗裂防水砂浆，对墙面进行找平	14.36	8.25	2.13	5.00	25.98	241.61	9.00	263.35
涂刷防水涂料2遍	19.86	11.76	2.13	5.00	35.44	659.18	9.00	718.51
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm厚	19.86	11.76	2.13	5.00	35.44	659.18	9.00	718.51
涂刷界面剂	4.77	7.65	1.26	5.00	14.36	222.58	9.00	242.61
提高界面处理剂	4.77	7.65	1.26	5.00	14.36	222.58	9.00	242.61
外墙表面铲除清理	14.73		2.43	5.00	18.02	279.31	9.00	304.45
对原墙面落灰、起皮的地方进行铲除	14.73		2.43	5.00	18.02	279.31	9.00	304.45
外墙涂料	12.13	8.16	1.97	5.00	23.37	478.15	9.00	521.18
外墙涂料一底二面	12.13	8.16	1.97	5.00	23.37	478.15	9.00	521.18
36-101南阳台外墙漏水	246.14	140.4	723.2	40.00	1,165.23	5,326.26	72.00	5,805.62
表面垃圾清理	14.73		2.43	5.00	18.02	259.49	9.00	282.84
对原墙面垃圾清理	14.73		2.43	5.00	18.02	259.49	9.00	282.84
窗口打胶	95.13	65.32	1.26	5.00	169.80	339.60	9.00	370.16
窗口原密封胶铲除，重新打硅宝结构耐候胶	95.13	65.32	1.26	5.00	169.80	339.60	9.00	370.16
大理石缝隙处打胶	11.65	14.51	4.21	5.00	31.89	918.43	9.00	1,001.09
大理石原密封胶铲除，重新打硅宝结构耐候胶	11.65	14.51	4.21	5.00	31.89	918.43	9.00	1,001.09
接缝处打胶	35.25	21.52	4.21	5.00	64.03	1,290.84	9.00	1,407.02
对大理石与外墙面接缝处，原密封胶铲除，重新打硅宝	35.25	21.52	4.21	5.00	64.03	1,290.84	9.00	1,407.02
垃圾清理	13.16		3.52	5.00	17.51	87.55	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	87.55	9.00	95.43
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
涂刷防水涂料2遍	33.32	24.54	3.36	5.00	64.28	1,203.32	9.00	1,311.62
涂刷东方雨虹HCA121透明防水涂料	33.32	24.54	3.36	5.00	64.28	1,203.32	9.00	1,311.62
涂刷界面剂	11.65	14.51	4.21	5.00	31.89	459.22	9.00	500.55
提高界面处理剂	11.65	14.51	4.21	5.00	31.89	459.22	9.00	500.55
36-101南主卧外墙漏水	246.14	140.4	723.2	40.00	1,165.23	4,476.76	72.00	4,879.66
表面垃圾清理	14.73		2.43	5.00	18.02	207.23	9.00	225.88
对原墙面垃圾清理	14.73		2.43	5.00	18.02	207.23	9.00	225.88
窗口打胶	95.13	65.32	1.26	5.00	169.80	339.60	9.00	370.16
窗口原密封胶铲除，重新打硅宝结构耐候胶	95.13	65.32	1.26	5.00	169.80	339.60	9.00	370.16
大理石缝隙处打胶	11.65	14.51	4.21	5.00	31.89	733.47	9.00	799.48
大理石原密封胶铲除，重新打硅宝结构耐候胶	11.65	14.51	4.21	5.00	31.89	733.47	9.00	799.48
接缝处打胶	35.25	21.52	4.21	5.00	64.03	1,030.88	9.00	1,123.66
对大理石与外墙面接缝处，原密封胶铲除，重新打硅宝	35.25	21.52	4.21	5.00	64.03	1,030.88	9.00	1,123.66
垃圾清理	13.16		3.52	5.00	17.51	70.04	9.00	76.34
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	70.04	9.00	76.34
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91



涂刷防水涂料2遍	33.32	24.54	3.36	5.00	64.28	960.99	9.00	1,047.48
涂刷东方雨虹HCA121透明防水涂料	33.32	24.54	3.36	5.00	64.28	960.99	9.00	1,047.48
涂刷界面剂	11.65	14.51	4.21	5.00	31.89	366.74	9.00	399.75
墙高界面处理剂	11.65	14.51	4.21	5.00	31.89	366.74	9.00	399.75
36-301北阳台东外墙滴水	314.32	161.02	738.6	50.00	1,274.63	3,677.45	90.00	4,008.42
窗口打胶	95.13	65.32	12.41	5.00	181.50	0.00	9.00	0.00
窗口原密封胶铲除，重新打硅宝结构耐候胶	95.13	65.32	12.41	5.00	181.50	0.00	9.00	0.00
堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
采用YH东方雨虹对缝隔堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
接缝处打胶	11.65	14.51	4.21	5.00	31.89	250.02	9.00	272.52
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝胶	11.65	14.51	4.21	5.00	31.89	250.02	9.00	272.52
垃圾清理	13.16		3.52	5.00	17.51	122.67	9.00	133.60
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	122.67	9.00	133.60
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平	14.36	8.25	2.13	5.00	25.98	305.52	9.00	333.02
采用立邦抗裂耐水砂浆，对墙面进行找平	14.36	8.25	2.13	5.00	25.98	305.52	9.00	333.02
涂刷防水涂料2遍	19.86	11.76	2.13	5.00	35.44	833.55	9.00	908.57
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm厚	19.86	11.76	2.13	5.00	35.44	833.55	9.00	908.57
涂刷界面剂	4.77	7.65	1.26	5.00	14.36	281.46	9.00	306.79
墙高界面处理剂	4.77	7.65	1.26	5.00	14.36	281.46	9.00	306.79
外墙表面铲除清理	14.73		2.43	5.00	18.02	353.19	9.00	384.98
对原墙面落灰、起皮的地方进行铲除	14.73		2.43	5.00	18.02	353.19	9.00	384.98
外墙涂料	12.13	8.16	1.97	5.00	23.37	601.58	9.00	658.99
外墙溶剂涂料一底二面	12.13	8.16	1.97	5.00	23.37	601.58	9.00	658.99
36-301东阳台东外墙滴水	314.32	161.02	738.6	50.00	1,274.63	4,370.50	90.00	4,763.85
窗口打胶	95.13	65.32	12.41	5.00	181.50	726.00	9.00	791.31
窗口原密封胶铲除，重新打硅宝结构耐候胶	95.13	65.32	12.41	5.00	181.50	726.00	9.00	791.31
堵漏	97.28	45.37	8.54	5.00	158.75	317.50	9.00	346.08
采用YH东方雨虹对缝隔堵漏	97.28	45.37	8.54	5.00	158.75	317.50	9.00	346.08
接缝处打胶	11.65	14.51	4.21	5.00	31.89	233.43	9.00	254.44
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝胶	11.65	14.51	4.21	5.00	31.89	233.43	9.00	254.44
垃圾清理	13.16		3.52	5.00	17.51	105.06	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	105.06	9.00	114.52
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平	14.36	8.25	2.13	5.00	25.98	285.26	9.00	310.93
采用立邦抗裂耐水砂浆，对墙面进行找平	14.36	8.25	2.13	5.00	25.98	285.26	9.00	310.93
涂刷防水涂料2遍	19.86	11.76	2.13	5.00	35.44	778.26	9.00	848.30
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm厚	19.86	11.76	2.13	5.00	35.44	778.26	9.00	848.30
涂刷界面剂	4.77	7.65	1.26	5.00	14.36	262.79	9.00	286.44
墙高界面处理剂	4.77	7.65	1.26	5.00	14.36	262.79	9.00	286.44
外墙表面铲除清理	14.73		2.43	5.00	18.02	329.77	9.00	359.45
对原墙面落灰、起皮的地方进行铲除	14.73		2.43	5.00	18.02	329.77	9.00	359.45
外墙涂料	12.13	8.16	1.97	5.00	23.37	564.62	9.00	615.44
外墙溶剂涂料一底二面	12.13	8.16	1.97	5.00	23.37	564.62	9.00	615.44
36-301北阳台北墙面	314.32	161.02	738.6	50.00	1,274.63	3,321.67	90.00	3,620.52
窗口打胶	95.13	65.32	12.41	5.00	181.50	363.00	9.00	395.67
窗口原密封胶铲除，重新打硅宝结构耐候胶	95.13	65.32	12.41	5.00	181.50	363.00	9.00	395.67
堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
采用YH东方雨虹对缝隔堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
接缝处打胶	11.65	14.51	4.21	5.00	31.89	184.96	9.00	201.61



对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝胶	11.65	14.51	4.21	5.00	31.89	184.96	9.00	201.61
垃圾清理	13.16		3.52	5.00	17.51	87.55	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	87.55	9.00	95.43
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平	14.36	8.25	2.13	5.00	25.98	226.03	9.00	246.37
采用立邦抗裂耐水砂浆，对墙面进行找平	14.36	8.25	2.13	5.00	25.98	226.03	9.00	246.37
涂刷防水涂料2遍	19.86	11.76	2.13	5.00	35.44	616.66	9.00	672.16
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm厚	19.86	11.76	2.13	5.00	35.44	616.66	9.00	672.16
涂刷界面剂	4.77	7.65	1.26	5.00	14.36	268.22	9.00	226.96
墙高界面处理剂	4.77	7.65	1.26	5.00	14.36	268.22	9.00	226.96
外墙表面铲除清理	14.73		2.43	5.00	18.02	261.29	9.00	284.81
对原墙面落灰、起皮的地方进行铲除	14.73		2.43	5.00	18.02	261.29	9.00	284.81
外墙涂料	12.13	8.16	1.97	5.00	23.37	447.30	9.00	487.56
外墙涂料一底二面	12.13	8.16	1.97	5.00	23.37	447.30	9.00	487.56
36-501主楼南墙	314.32	161.02	738.6	50.00	1,274.63	3,774.39	90.00	4,114.11
窗口打胶	95.13	65.32	12.41	5.00	181.50	181.50	9.00	197.84
窗口原密封胶铲除，重新打硅宝胶耐候胶	95.13	65.32	12.41	5.00	181.50	181.50	9.00	197.84
堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
采用YH东方雨虹对缝堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
接缝处打胶	11.65	14.51	4.21	5.00	31.89	243.64	9.00	265.57
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝胶	11.65	14.51	4.21	5.00	31.89	243.64	9.00	265.57
垃圾清理	13.16		3.52	5.00	17.51	105.06	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	105.06	9.00	114.52
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平	14.36	8.25	2.13	5.00	25.98	297.73	9.00	324.53
采用立邦抗裂耐水砂浆，对墙面进行找平	14.36	8.25	2.13	5.00	25.98	297.73	9.00	324.53
涂刷防水涂料2遍	19.86	11.76	2.13	5.00	35.44	812.28	9.00	885.39
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm厚	19.86	11.76	2.13	5.00	35.44	812.28	9.00	885.39
涂刷界面剂	4.77	7.65	1.26	5.00	14.36	274.28	9.00	298.97
墙高界面处理剂	4.77	7.65	1.26	5.00	14.36	274.28	9.00	298.97
外墙表面铲除清理	14.73		2.43	5.00	18.02	344.18	9.00	375.16
对原墙面落灰、起皮的地方进行铲除	14.73		2.43	5.00	18.02	344.18	9.00	375.16
外墙涂料	12.13	8.16	1.97	5.00	23.37	589.16	9.00	642.18
外墙涂料一底二面	12.13	8.16	1.97	5.00	23.37	589.16	9.00	642.18
36-901主楼东南角窗台下墙边	314.32	161.02	738.6	50.00	1,274.63	3,685.44	90.00	4,017.14
窗口打胶	95.13	65.32	12.41	5.00	181.50	181.50	9.00	197.84
窗口原密封胶铲除，重新打硅宝胶耐候胶	95.13	65.32	12.41	5.00	181.50	181.50	9.00	197.84
堵漏	97.28	45.37	8.54	5.00	158.75	476.25	9.00	519.11
采用YH东方雨虹对缝堵漏	97.28	45.37	8.54	5.00	158.75	476.25	9.00	519.11
接缝处打胶	11.65	14.51	4.21	5.00	31.89	206.65	9.00	225.25
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝胶	11.65	14.51	4.21	5.00	31.89	206.65	9.00	225.25
垃圾清理	13.16		3.52	5.00	17.51	87.55	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	87.55	9.00	95.43
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平	14.36	8.25	2.13	5.00	25.98	252.53	9.00	275.26
采用立邦抗裂耐水砂浆，对墙面进行找平	14.36	8.25	2.13	5.00	25.98	252.53	9.00	275.26
涂刷防水涂料2遍	19.86	11.76	2.13	5.00	35.44	688.95	9.00	750.96
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm厚	19.86	11.76	2.13	5.00	35.44	688.95	9.00	750.96
涂刷界面剂	4.77	7.65	1.26	5.00	14.36	232.63	9.00	253.57



墙高界面处理剂	4.77	7.65	1.26	5.00	14.36	232.63	9.00	253.57
外墙表面铲除清理	14.73		2.43	5.00	18.02	291.92	9.00	318.19
对原墙面落灰、起皮的地方进行铲除	14.73		2.43	5.00	18.02	291.92	9.00	318.19
外墙涂料	12.13	8.16	1.97	5.00	23.37	499.65	9.00	514.62
外墙溶剂涂料一底二面	12.13	8.16	1.97	5.00	23.37	499.65	9.00	514.62
37-101南阳台雨水主管更换	366.58	232.11	747.31	30.00	1,413.29	2,041.26	54.00	2,224.98
160PVC管	95.17	81.62	12.41	5.00	198.66	397.32	9.00	433.08
160PVC管道安装	95.17	81.62	12.41	5.00	198.66	397.32	9.00	433.08
160PVC直接	35.45	15.35	1.26	5.00	54.66	109.32	9.00	119.16
160PVC直接安装	35.45	15.35	1.26	5.00	54.66	109.32	9.00	119.16
堵漏	115.73	135.14	12.56	5.00	276.60	553.20	9.00	602.99
采用YH东方雨虹对管道上水口及下水口堵漏	115.73	135.14	12.56	5.00	276.60	553.20	9.00	602.99
管道基础拆除	75.82		17.56	5.00	98.05	196.10	9.00	213.75
对原160PVC管混凝土基础拆除	75.82		17.56	5.00	98.05	196.10	9.00	213.75
垃圾清理	13.16		3.52	5.00	17.51	17.51	9.00	19.09
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	17.51	9.00	19.09
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
37-101北卧室外墙漏水	314.32	161.02	738.6	50.00	1,274.63	3,470.93	90.00	3,783.31
窗口打胶	95.13	65.32	12.41	5.00	181.50	181.50	9.00	197.84
窗口原密封胶铲除，重新打硅宝结构耐候胶	95.13	65.32	12.41	5.00	181.50	181.50	9.00	197.84
堵漏	97.28	45.37	8.54	5.00	158.75	476.25	9.00	519.11
采用YH东方雨虹对缝隙堵漏	97.28	45.37	8.54	5.00	158.75	476.25	9.00	519.11
接缝处打胶	11.65	14.51	4.21	5.00	31.89	186.24	9.00	203.00
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝结	11.65	14.51	4.21	5.00	31.89	186.24	9.00	203.00
垃圾清理	13.16		3.52	5.00	17.51	87.55	9.00	95.43
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	87.55	9.00	95.43
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平	14.36	8.25	2.13	5.00	25.98	227.58	9.00	218.06
采用立邦抗裂防水砂浆，对墙面进行找平	14.36	8.25	2.13	5.00	25.98	227.58	9.00	218.06
涂刷防水涂料2遍	19.86	11.76	2.13	5.00	35.44	620.91	9.00	676.79
涂刷东方雨虹K11-108厨卫外墙高弹性防水涂料1.5mm厚	19.86	11.76	2.13	5.00	35.44	620.91	9.00	676.79
涂刷界面剂	4.77	7.65	1.26	5.00	14.36	209.66	9.00	228.53
墙高界面处理剂	4.77	7.65	1.26	5.00	14.36	209.66	9.00	228.53
外墙表面铲除清理	14.73		2.43	5.00	18.02	263.09	9.00	286.77
对原墙面落灰、起皮的地方进行铲除	14.73		2.43	5.00	18.02	263.09	9.00	286.77
外墙涂料	12.13	8.16	1.97	5.00	23.37	450.34	9.00	490.87
外墙溶剂涂料一底二面	12.13	8.16	1.97	5.00	23.37	450.34	9.00	490.87
37-602南卧室外墙漏水	314.32	161.02	738.6	50.00	1,274.63	3,640.29	90.00	3,967.92
窗口打胶	95.13	65.32	12.41	5.00	181.50	181.50	9.00	197.84
窗口原密封胶铲除，重新打硅宝结构耐候胶	95.13	65.32	12.41	5.00	181.50	181.50	9.00	197.84
堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
采用YH东方雨虹对缝隙堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
接缝处打胶	11.65	14.51	4.21	5.00	31.89	230.88	9.00	251.66
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝结	11.65	14.51	4.21	5.00	31.89	230.88	9.00	251.66
垃圾清理	13.16		3.52	5.00	17.51	105.06	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	105.06	9.00	114.52
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平	14.36	8.25	2.13	5.00	25.98	282.14	9.00	307.53
采用立邦抗裂防水砂浆，对墙面进行找平	14.36	8.25	2.13	5.00	25.98	282.14	9.00	307.53

涂刷防水涂料2遍	19.86	11.76	2.13	5.00	35.44	769.76	9.00	839.04
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm厚	19.86	11.76	2.13	5.00	35.44	769.76	9.00	839.04
涂刷界面剂	4.77	7.65	1.26	5.00	14.36	259.92	9.00	283.31
墙高界面处理剂	4.77	7.65	1.26	5.00	11.36	259.92	9.00	283.31
外墙表面铲除清理	14.73		2.43	5.00	18.02	326.16	9.00	355.51
对原墙面落灰、起皮的地方进行铲除	14.73		2.43	5.00	18.02	326.16	9.00	355.51
外墙涂料	12.13	8.16	1.97	5.00	23.37	558.31	9.00	608.56
外墙溶剂涂料一底二面	12.13	8.16	1.97	5.00	23.37	558.31	9.00	608.56
37-701南阳台外墙	314.32	161.02	738.6	50.00	1,274.63	3,701.04	90.00	4,034.14
窗口打胶	95.13	65.32	12.41	5.00	181.50	363.00	9.00	395.67
窗口原密封胶铲除，重新打硅宝结构耐候胶	95.13	65.32	12.41	5.00	181.50	363.00	9.00	395.67
堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
采用YH东方雨虹对缝限堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
接缝处打胶	11.65	14.51	4.21	5.00	31.89	219.40	9.00	239.15
对窗台与外墙面接缝处，以密封胶铲除，重新打硅宝结	11.65	14.51	4.21	5.00	31.89	219.40	9.00	239.15
垃圾清理	13.16		3.52	5.00	17.51	105.06	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	105.06	9.00	114.52
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平	14.36	8.25	2.13	5.00	25.98	268.11	9.00	292.24
采用立邦抗裂耐水砂浆，对墙面进行找平	14.36	8.25	2.13	5.00	25.98	268.11	9.00	292.24
涂刷防水涂料2遍	19.86	11.76	2.13	5.00	35.44	731.48	9.00	797.31
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm厚	19.86	11.76	2.13	5.00	35.44	731.48	9.00	797.31
涂刷界面剂	4.77	7.65	1.26	5.00	11.36	216.99	9.00	269.22
墙高界面处理剂	4.77	7.65	1.26	5.00	14.36	216.99	9.00	269.22
外墙表面铲除清理	14.73		2.43	5.00	18.02	309.94	9.00	347.88
对原墙面落灰、起皮的地方进行铲除	14.73		2.43	5.00	18.02	309.94	9.00	347.88
外墙涂料	12.13	8.16	1.97	5.00	23.37	530.50	9.00	578.25
外墙溶剂涂料一底二面	12.13	8.16	1.97	5.00	23.37	530.50	9.00	578.25
37-801南阳台外墙	314.32	161.02	738.6	50.00	1,274.63	3,754.75	90.00	4,062.68
窗口打胶	95.13	65.32	12.41	5.00	181.50	363.00	9.00	395.67
窗口原密封胶铲除，重新打硅宝结构耐候胶	95.13	65.32	12.41	5.00	181.50	363.00	9.00	395.67
堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
采用YH东方雨虹对缝限堵漏	97.28	45.37	8.54	5.00	158.75	158.75	9.00	173.04
接缝处打胶	11.65	14.51	4.21	5.00	31.89	224.51	9.00	244.72
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝结	11.65	14.51	4.21	5.00	31.89	224.51	9.00	244.72
垃圾清理	13.16		3.52	5.00	17.51	105.06	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	13.16		3.52	5.00	17.51	105.06	9.00	114.52
垃圾装车外运	31.25		700	5.00	767.81	767.81	9.00	836.91
自卸汽车运土（8t以内）（运距25km以内）	31.25		700	5.00	767.81	767.81	9.00	836.91
砂浆抹面找平	14.36	8.25	2.13	5.00	25.98	274.35	9.00	299.04
采用立邦抗裂耐水砂浆，对墙面进行找平	14.36	8.25	2.13	5.00	25.98	274.35	9.00	299.04
涂刷防水涂料2遍	19.86	11.76	2.13	5.00	35.44	748.49	9.00	815.85
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料1.5mm厚	19.86	11.76	2.13	5.00	35.44	748.49	9.00	815.85
涂刷界面剂	4.77	7.65	1.26	5.00	14.36	252.74	9.00	275.49
墙高界面处理剂	4.77	7.65	1.26	5.00	14.36	252.74	9.00	275.49
外墙表面铲除清理	14.73		2.43	5.00	18.02	317.15	9.00	345.69
对原墙面落灰、起皮的地方进行铲除	14.73		2.43	5.00	18.02	317.15	9.00	345.69
外墙涂料	12.13	8.16	1.97	5.00	23.37	542.89	9.00	591.75
外墙溶剂涂料一底二面	12.13	8.16	1.97	5.00	23.37	542.89	9.00	591.75