

天鹤湖花园B区房屋渗水维修工程预算

行标签	求和项:数量	求和项:人工	求和项:主材	求和项:机械辅材	求和项:不含税单价	平均值项:综合取费	平均值项:税率	求和项:含税合价
126	1096.58	3157.78	3202.2	4003.52	10,881.60	5.00	9.00	48,904.08
126-102北卧室北外墙漏水	89.35	259.23	258.92	391.19	954.80	5.00	9.00	4,493.93
表面清理	13.5	15.56		2.43	18.89	5.00	9.00	277.97
对原墙面落灰、起皮的地方进行铲除	13.5	15.56		2.43	18.89	5.00	9.00	277.97
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除,重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
大理石缝隙处打胶	20.25	12	15	4	32.55	5.00	9.00	718.46
大理石原密封胶铲除,重新打硅宝结构耐候胶	20.25	12	15	4	32.55	5.00	9.00	718.46
接缝处打胶	18.9	35.25	21.52	4.21	64.03	5.00	9.00	1,319.09
对大理石与外墙面接缝处,原密封胶铲除,重新打	18.9	35.25	21.52	4.21	64.03	5.00	9.00	1,319.09
垃圾清理	5	13.16		3.52	17.51	5.00	9.00	95.43
人工清理建筑垃圾并装袋,垂直运输短驳	5	13.16		3.52	17.51	5.00	9.00	95.43
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土(8t以内)(运距25km以内)	1	50		360	430.50	5.00	9.00	469.25
涂刷防水涂料2遍	14.85	33.32	24.54	3.36	64.28	5.00	9.00	1,040.47
涂刷东方雨虹HCA121透明防水涂料	14.85	33.32	24.54	3.36	64.28	5.00	9.00	1,040.47
涂刷界面剂	14.85	4.77	7.65	1.26	14.36	5.00	9.00	232.44
德高界面处理剂	14.85	4.77	7.65	1.26	14.36	5.00	9.00	232.44
126-102卧室南外墙漏水	114.75	259.23	258.92	391.19	954.80	5.00	9.00	5,576.26
表面清理	17.5	15.56		2.43	18.89	5.00	9.00	360.33
对原墙面落灰、起皮的地方进行铲除	17.5	15.56		2.43	18.89	5.00	9.00	360.33
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除,重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
大理石缝隙处打胶	26.25	12	15	4	32.55	5.00	9.00	931.34
大理石原密封胶铲除,重新打硅宝结构耐候胶	26.25	12	15	4	32.55	5.00	9.00	931.34
接缝处打胶	24.5	35.25	21.52	4.21	64.03	5.00	9.00	1,709.93
对大理石与外墙面接缝处,原密封胶铲除,重新打	24.5	35.25	21.52	4.21	64.03	5.00	9.00	1,709.93
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋,垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土(8t以内)(运距25km以内)	1	50		360	430.50	5.00	9.00	469.25
涂刷防水涂料2遍	19.25	33.32	24.54	3.36	64.28	5.00	9.00	1,348.76
涂刷东方雨虹HCA121透明防水涂料	19.25	33.32	24.54	3.36	64.28	5.00	9.00	1,348.76
涂刷界面剂	19.25	4.77	7.65	1.26	14.36	5.00	9.00	301.31
德高界面处理剂	19.25	4.77	7.65	1.26	14.36	5.00	9.00	301.31
126-1201南主卧南外墙漏水	101.49	364.21	391.87	402.61	1,216.62	5.00	9.00	4,162.31
表面清理	17.6	15.56		2.43	18.89	5.00	9.00	362.38
对原墙面落灰、起皮的地方进行铲除	17.6	15.56		2.43	18.89	5.00	9.00	362.38
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除,重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.28	12	15	4	32.55	5.00	9.00	187.33
对窗台与外墙面接缝处,原密封胶铲除,重新打	5.28	12	15	4	32.55	5.00	9.00	187.33
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋,垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土(8t以内)(运距25km以内)	1	50		360	430.50	5.00	9.00	469.25
抹灰	10.56	20.66	10.51	2.33	35.18	5.00	9.00	404.94
水泥砂浆抹灰	10.56	20.66	10.51	2.33	35.18	5.00	9.00	404.94
涂刷防水涂料2遍	19.36	28.6	21.2	2.13	54.53	5.00	9.00	1,150.71
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	19.36	28.6	21.2	2.13	54.53	5.00	9.00	1,150.71
涂刷界面剂	19.36	4.77	7.65	1.26	14.36	5.00	9.00	303.03
德高界面处理剂	19.36	4.77	7.65	1.26	14.36	5.00	9.00	303.03
外墙涂料	20.33	8.56	12.16	1.97	23.82	5.00	9.00	527.84
外墙溶剂涂料一底二面	20.33	8.56	12.16	1.97	23.82	5.00	9.00	527.84
126-1401南阳台南外墙开裂漏水	118.73	364.21	391.87	402.61	1,216.62	5.00	9.00	4,966.72
表面清理	20.5	15.56		2.43	18.89	5.00	9.00	422.10
对原墙面落灰、起皮的地方进行铲除	20.5	15.56		2.43	18.89	5.00	9.00	422.10
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除,重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	2	115.73	135.14	12.56	276.60	5.00	9.00	602.99
采用YH东方雨虹对缝堵漏	2	115.73	135.14	12.56	276.60	5.00	9.00	602.99
接缝处打胶	6.15	12	15	4	32.55	5.00	9.00	218.20
对窗台与外墙面接缝处,原密封胶铲除,重新打	6.15	12	15	4	32.55	5.00	9.00	218.20
垃圾清理	7	13.16		3.52	17.51	5.00	9.00	133.60
人工清理建筑垃圾并装袋,垂直运输短驳	7	13.16		3.52	17.51	5.00	9.00	133.60
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土(8t以内)(运距25km以内)	1	50		360	430.50	5.00	9.00	469.25
抹灰	12.3	20.66	10.51	2.33	35.18	5.00	9.00	471.65
水泥砂浆抹灰	12.3	20.66	10.51	2.33	35.18	5.00	9.00	471.65
涂刷防水涂料2遍	22.55	28.6	21.2	2.13	54.53	5.00	9.00	1,340.32
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	22.55	28.6	21.2	2.13	54.53	5.00	9.00	1,340.32
涂刷界面剂	22.55	4.77	7.65	1.26	14.36	5.00	9.00	352.96
德高界面处理剂	22.55	4.77	7.65	1.26	14.36	5.00	9.00	352.96
外墙涂料	23.68	8.56	12.16	1.97	23.82	5.00	9.00	614.83
外墙溶剂涂料一底二面	23.68	8.56	12.16	1.97	23.82	5.00	9.00	614.83
126-1702主卧阳台东墙保温层脱落	164.52	227.03	166.57	402.74	836.14	5.00	9.00	8,055.13

安装保温板	16.8	20.17	28.52	8.12	59.65	5.00	9.00	1,092.31
安装5cm厚高密度聚苯乙烯树脂板	16.8	20.17	28.52	8.12	59.65	5.00	9.00	1,092.31
底层抹灰	16.8	12.31	16.82	2.75	33.47	5.00	9.00	612.91
抗裂砂浆找平	16.8	12.31	16.82	2.75	33.47	5.00	9.00	612.91
挂玻纤网	18.48	11.15	4.58	0.86	17.42	5.00	9.00	350.89
3*3mm高密度玻璃纤维网	18.48	11.15	4.58	0.86	17.42	5.00	9.00	350.89
垃圾清理	3	13.16		3.52	17.51	5.00	9.00	57.26
人工清理建筑垃圾并装袋，垂直运输短驳	3	13.16		3.52	17.51	5.00	9.00	57.26
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
批腻子2遍	19.4	22.15	28.71	3.84	57.44	5.00	9.00	1,214.63
立邦外墙专用腻子	19.4	22.15	28.71	3.84	57.44	5.00	9.00	1,214.63
刷抗裂砂浆2遍	16.8	22.15	27.86	3.45	56.13	5.00	9.00	1,027.85
刷立邦抗裂耐水砂浆2遍	16.8	22.15	27.86	3.45	56.13	5.00	9.00	1,027.85
刷墙固	18.48	11.17	15.45	3.25	31.36	5.00	9.00	631.69
涂刷表面处理剂	18.48	11.17	15.45	3.25	31.36	5.00	9.00	631.69
刷外墙涂料	18.48	8.56	12.16	1.97	23.82	5.00	9.00	479.81
外墙溶剂涂料一底二面	18.48	8.56	12.16	1.97	23.82	5.00	9.00	479.81
涂刷防水涂料2遍	18.48	25.65	32.47	7.13	68.51	5.00	9.00	1,380.01
涂刷丙烯酸防水涂料2遍	18.48	25.65	32.47	7.13	68.51	5.00	9.00	1,380.01
外墙打开保温层	16.8	30.56		7.85	40.33	5.00	9.00	738.52
蜘蛛人高空对外墙面及保温层拆除	16.8	30.56		7.85	40.33	5.00	9.00	738.52
126-1802主卧阳台东墙保温层脱落	75.66	227.03	166.57	402.74	836.14	5.00	9.00	3,887.48
安装保温板	7.5	20.17	28.52	8.12	59.65	5.00	9.00	487.64
安装5cm厚高密度聚苯乙烯树脂板	7.5	20.17	28.52	8.12	59.65	5.00	9.00	487.64
底层抹灰	7.5	12.31	16.82	2.75	33.47	5.00	9.00	273.62
抗裂砂浆找平	7.5	12.31	16.82	2.75	33.47	5.00	9.00	273.62
挂玻纤网	8.25	11.15	4.58	0.86	17.42	5.00	9.00	156.65
3*3mm高密度玻璃纤维网	8.25	11.15	4.58	0.86	17.42	5.00	9.00	156.65
垃圾清理	3	13.16		3.52	17.51	5.00	9.00	57.26
人工清理建筑垃圾并装袋，垂直运输短驳	3	13.16		3.52	17.51	5.00	9.00	57.26
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
批腻子2遍	8.66	22.15	28.71	3.84	57.44	5.00	9.00	542.20
立邦外墙专用腻子	8.66	22.15	28.71	3.84	57.44	5.00	9.00	542.20
刷抗裂砂浆2遍	7.5	22.15	27.86	3.45	56.13	5.00	9.00	458.87
刷立邦抗裂耐水砂浆2遍	7.5	22.15	27.86	3.45	56.13	5.00	9.00	458.87
刷墙固	8.25	11.17	15.45	3.25	31.36	5.00	9.00	282.00
涂刷表面处理剂	8.25	11.17	15.45	3.25	31.36	5.00	9.00	282.00
刷外墙涂料	8.25	8.56	12.16	1.97	23.82	5.00	9.00	214.21
外墙溶剂涂料一底二面	8.25	8.56	12.16	1.97	23.82	5.00	9.00	214.21
涂刷防水涂料2遍	8.25	25.65	32.47	7.13	68.51	5.00	9.00	616.08
涂刷丙烯酸防水涂料2遍	8.25	25.65	32.47	7.13	68.51	5.00	9.00	616.08
外墙打开保温层	7.5	30.56		7.85	40.33	5.00	9.00	329.70
蜘蛛人高空对外墙面及保温层拆除	7.5	30.56		7.85	40.33	5.00	9.00	329.70
126-502南主卧南外墙漏水	100.39	364.21	391.87	402.61	1,216.62	5.00	9.00	4,515.05
表面清理	17.2	15.56		2.43	18.89	5.00	9.00	354.15
对原墙面落灰、起皮的地方进行铲除	17.2	15.56		2.43	18.89	5.00	9.00	354.15
窗口打胶	2	95.17	190.21	12.41	312.68	5.00	9.00	651.64
窗口原密封胶铲除，重新打硅宝结构耐候胶	2	95.17	190.21	12.41	312.68	5.00	9.00	651.64
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.16	12	15	4	32.55	5.00	9.00	183.08
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝结构耐候胶	5.16	12	15	4	32.55	5.00	9.00	183.08
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
抹灰	10.32	20.66	10.51	2.33	35.18	5.00	9.00	395.74
水泥砂浆抹灰	10.32	20.66	10.51	2.33	35.18	5.00	9.00	395.74
涂刷防水涂料2遍	18.92	28.6	21.2	2.13	54.53	5.00	9.00	1,124.56
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	18.92	28.6	21.2	2.13	54.53	5.00	9.00	1,124.56
涂刷界面剂	18.92	4.77	7.65	1.26	14.36	5.00	9.00	296.14
德高界面处理剂	18.92	4.77	7.65	1.26	14.36	5.00	9.00	296.14
外墙涂料	19.87	8.56	12.16	1.97	23.82	5.00	9.00	515.90
外墙溶剂涂料一底二面	19.87	8.56	12.16	1.97	23.82	5.00	9.00	515.90
126-701南卧室东侧外墙漏水	113	364.21	391.87	402.61	1,216.62	5.00	9.00	4,515.05
表面清理	19.6	15.56		2.43	18.89	5.00	9.00	403.56
对原墙面落灰、起皮的地方进行铲除	19.6	15.56		2.43	18.89	5.00	9.00	403.56
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝隙堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.88	12	15	4	32.55	5.00	9.00	208.62
对窗台与外墙面接缝处，原密封胶铲除，重新打硅宝结构耐候胶	5.88	12	15	4	32.55	5.00	9.00	208.62
垃圾清理	7	13.16		3.52	17.51	5.00	9.00	133.60
人工清理建筑垃圾并装袋，垂直运输短驳	7	13.16		3.52	17.51	5.00	9.00	133.60
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
抹灰	11.76	20.66	10.51	2.33	35.18	5.00	9.00	450.95

水泥砂浆抹灰	11.76	20.66	10.51	2.33	35.18	5.00	9.00	450.95
涂刷防水涂料2遍	21.56	28.6	21.2	2.13	54.53	5.00	9.00	1,281.48
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.56	28.6	21.2	2.13	54.53	5.00	9.00	1,281.48
涂刷界面剂	21.56	4.77	7.65	1.26	14.36	5.00	9.00	337.46
德高界面处理剂	21.56	4.77	7.65	1.26	14.36	5.00	9.00	337.46
外墙涂料	22.64	8.56	12.16	1.97	23.82	5.00	9.00	587.82
外墙溶剂涂料一底二面	22.64	8.56	12.16	1.97	23.82	5.00	9.00	587.82
126-702南主卧南外墙漏水	102.54	364.21	391.87	402.61	1,216.62	5.00	9.00	4,195.66
表面清理	17.8	15.56		2.43	18.89	5.00	9.00	366.50
对原墙面落灰、起皮的地方进行铲除	17.8	15.56		2.43	18.89	5.00	9.00	366.50
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	5.34	12	15	4	32.55	5.00	9.00	189.46
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	5.34	12	15	4	32.55	5.00	9.00	189.46
垃圾清理	6	13.16		3.52	17.51	5.00	9.00	114.52
人工清理建筑垃圾并装袋，垂直运输短驳	6	13.16		3.52	17.51	5.00	9.00	114.52
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
抹灰	10.68	20.66	10.51	2.33	35.18	5.00	9.00	409.53
水泥砂浆抹灰	10.68	20.66	10.51	2.33	35.18	5.00	9.00	409.53
涂刷防水涂料2遍	19.58	28.6	21.2	2.13	54.53	5.00	9.00	1,163.79
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	19.58	28.6	21.2	2.13	54.53	5.00	9.00	1,163.79
涂刷界面剂	19.58	4.77	7.65	1.26	14.36	5.00	9.00	306.48
德高界面处理剂	19.58	4.77	7.65	1.26	14.36	5.00	9.00	306.48
外墙涂料	20.56	8.56	12.16	1.97	23.82	5.00	9.00	533.82
外墙溶剂涂料一底二面	20.56	8.56	12.16	1.97	23.82	5.00	9.00	533.82
126-703南主卧南外墙漏水	116.15	364.21	391.87	402.61	1,216.62	5.00	9.00	4,615.07
表面清理	20.2	15.56		2.43	18.89	5.00	9.00	415.92
对原墙面落灰、起皮的地方进行铲除	20.2	15.56		2.43	18.89	5.00	9.00	415.92
窗口打胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
窗口原密封胶铲除，重新打硅宝结构耐候胶	1	95.17	190.21	12.41	312.68	5.00	9.00	340.82
堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
采用YH东方雨虹对缝堵漏	1	115.73	135.14	12.56	276.60	5.00	9.00	301.49
接缝处打胶	6.06	12	15	4	32.55	5.00	9.00	215.00
对窗台与外墙面接缝处，原密封胶铲除，重新打胶	6.06	12	15	4	32.55	5.00	9.00	215.00
垃圾清理	7	13.16		3.52	17.51	5.00	9.00	133.60
人工清理建筑垃圾并装袋，垂直运输短驳	7	13.16		3.52	17.51	5.00	9.00	133.60
垃圾外运	1	50		360	430.50	5.00	9.00	469.25
自卸汽车运土（8t以内）（运距25km以内）	1	50		360	430.50	5.00	9.00	469.25
抹灰	12.12	20.66	10.51	2.33	35.18	5.00	9.00	464.75
水泥砂浆抹灰	12.12	20.66	10.51	2.33	35.18	5.00	9.00	464.75
涂刷防水涂料2遍	22.22	28.6	21.2	2.13	54.53	5.00	9.00	1,320.71
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	22.22	28.6	21.2	2.13	54.53	5.00	9.00	1,320.71
涂刷界面剂	22.22	4.77	7.65	1.26	14.36	5.00	9.00	347.80
德高界面处理剂	22.22	4.77	7.65	1.26	14.36	5.00	9.00	347.80
外墙涂料	23.33	8.56	12.16	1.97	23.82	5.00	9.00	605.73
外墙溶剂涂料一底二面	23.33	8.56	12.16	1.97	23.82	5.00	9.00	605.73

