

行标签	求和项:数量:A	求和项:人工费(不含税):B	求和项:主材费(求和项:机械辅材费(求和项:综合取费(求和项:不含税单价:求和项:不含税:求和项:税率:求和项:含税价:J							
160	719	336.86	108.92	754.25	85.00	20,256.99	1,280.03	153.00	22,080.12	
160-501楼顶瓦片脱落修复	179	179	193.82	37.42	379.23	45.00	4,369.01	641.00	81.00	4,762.21
安装不锈钢U型槽	9	9	28.5	0	2.41	5.00	292.14	32.46	9.00	318.43
打硅宝结构耐候胶	9	35.25	21.52	4.21	5.00	5.00	576.27	64.03	9.00	628.13
底部铺设100mm*100mm木方用于固定瓦片	30	8.77	7.65	1.26	5.00	5.00	556.80	18.56	9.00	606.91
对开裂、破损的瓦片进行拆除	30	18.81	8.25	2.43	5.00	669.00	729.21	22.30	9.00	729.21
立邦抗裂防水砂浆抹面	30	6.18	8.25	2.13	5.00	521.70	568.65	17.39	9.00	568.65
人工清理建筑垃圾并装袋,垂直运输短驳	10	13.16	3.52	0.86	5.00	175.10	190.86	17.51	9.00	190.86
瓦片打孔	30	4.65	0	0.86	5.00	173.70	189.33	5.79	9.00	189.33
瓦片固定、安装	30	28.5	0	2.41	5.00	973.80	1,061.44	32.46	9.00	1,061.44
自卸汽车运土(8t以内)(运距25km以内)	1	50	360	5.00	430.50	9.00	469.25	430.50	9.00	469.25
160-502楼顶天沟渗水	540	143.04	71.5	375.02	40.00	15,887.98	17,317.91	619.03	72.00	17,317.91
德高界面处理剂	85	4.77	7.65	1.26	5.00	1,220.60	1,330.45	14.36	9.00	1,330.45
对原沟槽基面开裂、破损的地方进行铲除	85	18.81	2.43	5.00	1,895.50	2,006.10	2,006.10	22.30	9.00	2,006.10
高分子聚氨酯水性涂料一遍	85	12.15	15.35	2.13	5.00	2,644.35	2,882.54	31.11	9.00	2,882.54
聚氨酯高分子防腐防水底涂一遍	85	15.5	19.21	2.41	5.00	3,313.30	3,611.50	38.98	9.00	3,611.50
聚氨酯高分子防腐防水面涂一遍	85	15.5	19.21	2.41	5.00	3,313.30	3,611.50	38.98	9.00	3,611.50
铺设PVC400g聚酯布一层	85	13.15	10.08	0.86	5.00	2,149.65	2,343.12	25.29	9.00	2,343.12
人工清理建筑垃圾并装袋,垂直运输短驳	28	13.16	3.52	0.86	5.00	490.28	534.41	17.51	9.00	534.41
自卸汽车运土(8t以内)(运距25km以内)	2	50	360	5.00	430.50	861.00	938.49	430.50	9.00	938.49