

太湖国际二街区星辉公共区域111单元防水维修工程报价明细

五	42-111-601主卧外墙、窗户漏水					
1	现场临时围挡	m	40	4.5	180.00	
2	安全警戒及指导	项	1	200	200.00	
3	切割, 凿除表面, 清理至结构基层, 基层清洗冲刷	m²	6.3	54	340.20	
4	窗侧四周进行重新塞缝密实	m²	6.3	20.5	129.15	
5	大面积涂刷丙烯酸外墙防水2遍	m²	6.3	42.4	267.12	
6	淋水5小时不渗漏后, 进行外墙保温涂料的恢复	m²	6.3	12.6	79.38	
7	25厚防水砂浆	m²	6.3	38	239.40	
8	100厚挤塑板保温板铺贴	m²	6.3	40	252.00	
9	40厚细砂找平	m²	6.3	38	239.40	
10	采用耐碱玻纤网格布加固, 抗裂砂浆粉刷	m²	6.3	55	346.50	
11	外墙腻子批涂2遍	m²	6.3	25.8	162.54	
12	喷刷外墙涂料(外墙专用封闭底漆1遍, 面漆2遍)	m²	6.3	55	346.50	
13	吊篮租赁安拆(含移位)	m²	6.3	65	409.50	
14	垃圾搬运至指定地点及清运	m²	6.3	45	283.50	
15	小计				3475.19	
16	税金			6%	208.51	
17	含税合计				3683.70	
六	42-111-1002客厅东墙漏水					
1	现场临时围挡	m	40	4.5	180.00	
2	安全警戒及指导	项	1	200	200.00	
3	切割, 凿除表面, 清理至结构基层, 基层清洗冲刷	m²	9.6	54	518.40	
4	大面积涂刷丙烯酸外墙防水2遍	m²	9.6	42.4	407.04	
5	淋水5小时不渗漏后, 进行外墙保温涂料的恢复	m²	9.6	12.6	120.96	
6	25厚防水砂浆	m²	9.6	38	364.80	
7	100厚挤塑板保温板铺贴	m²	9.6	40	384.00	
8	40厚细砂找平	m²	9.6	38	364.80	
9	采用耐碱玻纤网格布加固, 抗裂砂浆粉刷	m²	9.6	55	528.00	
10	外墙腻子批涂2遍	m²	9.6	25.8	247.68	
11	喷刷外墙涂料(外墙专用封闭底漆1遍, 面漆2遍)	m²	9.6	55	528.00	
12	吊篮租赁安拆(含移位)	m²	9.6	65	624.00	
13	垃圾搬运至指定地点及清运	m²	9.6	45	432.00	
14	小计				4899.68	
15	税金			6%	293.98	
16	含税合计				5193.66	
七	42-111-1501主卧外墙、窗户漏水					
1	现场临时围挡	m	40	4.5	180.00	
2	安全警戒及指导	项	1	200	200.00	
3	切割, 凿除表面, 清理至结构基层, 基层清洗冲刷	m²	6.8	54	367.20	
4	窗侧四周进行重新塞缝密实	m²	6.8	20.5	139.40	
5	大面积涂刷丙烯酸外墙防水2遍	m²	6.8	42.4	288.32	
6	淋水5小时不渗漏后, 进行外墙保温涂料的恢复	m²	6.8	12.6	85.68	
7	25厚防水砂浆	m²	6.8	38	258.40	
8	100厚挤塑板保温板铺贴	m²	6.8	40	272.00	
9	40厚细砂找平	m²	6.8	38	258.40	
10	采用耐碱玻纤网格布加固, 抗裂砂浆粉刷	m²	6.8	55	374.00	
11	外墙腻子批涂2遍	m²	6.8	25.8	175.44	
12	喷刷外墙涂料(外墙专用封闭底漆1遍, 面漆2遍)	m²	6.8	55	374.00	
13	吊篮租赁安拆(含移位)	m²	6.8	65	442.00	
14	垃圾搬运至指定地点及清运	m²	6.8	45	306.00	
15	小计				3720.84	
16	税金			6%	223.25	
17	含税合计				3944.09	

汇总

12821.45