

天鹅湖花园B区房屋渗水维修工程预算							
行标签	求和项:人工费(不含税)	求和项:主材费(不含税)	求和项:机械辅材费(不含税)	平均值项:综合取费	求和项:不含税价	平均值项:税率(%)	求和项:含税价
169	2473.36	930.9	6563.08	5.00	91,475.30	9.00	99,708.10
169单元二楼南面阳台渗水	539.38	140.13	15.58	5.00	10,997.28	9.00	11,987.03
高空吊绳人工费	480			5.00	1,512.00	9.00	1,648.08
裂缝或起皮处修复(挂)	3	12	2	5.00	749.70	9.00	817.17
刷外墙涂料	23.38	30.13	5.58	5.00	2,605.68	9.00	2,840.19
外墙防水JS涂料(2遍)	15	42	3	5.00	2,646.00	9.00	2,884.14
外墙防水丙稀酸(2遍)	15	42	3	5.00	2,646.00	9.00	2,884.14
做底漆	3	14	2	5.00	837.90	9.00	913.31
169单元北面外墙空鼓脱落	303.76	136.54	1304.38	5.00	13,850.57	9.00	15,097.11
安装	17	22.7	8	5.00	2,003.60	9.00	2,183.92
打开墙面	31		2.43	5.00	1,404.00	9.00	1,530.36
底层抹灰	12	15.48	2	5.00	1,238.00	9.00	1,349.42
刮腻子	9	11	0.63	5.00	866.40	9.00	944.38
挂网	9	2.7	0.56	5.00	514.90	9.00	561.13
抗裂砂浆整体批刮	11	12.4	1.3	5.00	1,007.60	9.00	1,100.98
垃圾清理外运	157		1276	5.00	1,504.65	9.00	1,640.07
刷墙固	11	12	2.3	5.00	1,169.08	9.00	1,274.30
刷外墙涂料	46.76	60.26	11.16	5.00	5,707.68	9.00	6,221.37
169单元南面二楼外墙脱落	303.76	136.54	1304.38	5.00	16,342.65	9.00	17,813.50
安装	17	22.7	8	5.00	2,003.60	9.00	2,183.92
打开墙面	31		2.43	5.00	1,404.00	9.00	1,530.36
底层抹灰	12	15.48	2	5.00	1,238.00	9.00	1,349.42
刮腻子	9	11	0.63	5.00	866.40	9.00	944.38
挂网	9	2.7	0.56	5.00	514.90	9.00	561.13
抗裂砂浆整体批刮	11	12.4	1.3	5.00	1,007.60	9.00	1,100.98
垃圾清理外运	157		1276	5.00	1,504.65	9.00	1,640.07
刷墙固	11	12	2.3	5.00	1,169.08	9.00	1,274.30
刷外墙涂料	46.76	60.26	11.16	5.00	5,707.68	9.00	6,221.37
169单元三楼南面阳台渗水	539.38	140.13	15.58	5.00	13,707.36	9.00	14,941.02
高空吊绳人工费	480			5.00	1,512.00	9.00	1,648.08
裂缝或起皮处修复(挂)	3	12	2	5.00	963.90	9.00	1,050.65
刷外墙涂料	23.38	30.13	5.58	5.00	3,350.16	9.00	3,651.67
外墙防水JS涂料(2遍)	15	42	3	5.00	3,402.00	9.00	3,708.18
外墙防水丙稀酸(2遍)	15	42	3	5.00	3,402.00	9.00	3,708.18
做底漆	3	14	2	5.00	1,077.30	9.00	1,174.26
169单元四楼北面阳台渗水	241.66	120.51	1303.11	5.00	12,310.05	9.00	13,417.97
SBS防水卷材铺设	15	50	10	5.00	5,197.50	9.00	5,665.28
场地整平、表面垃圾清	25		3.78	5.00	1,994.52	9.00	2,174.03
高压注浆	20	52	10	5.00	861.00	9.00	938.49
聚氨酯防水一遍	20.66	10.51	2.33	5.00	2,321.88	9.00	2,530.85
垃圾清理外运	157		1276	5.00	1,504.65	9.00	1,640.07
去灰型底油	2	3	0	5.00	346.50	9.00	377.69
钻洞并装置注浆针头	2	5	1	5.00	84.00	9.00	91.56
169单元四楼南面阳台渗水	241.66	120.51	1315.67	5.00	9,766.20	9.00	10,645.16
SBS防水卷材铺设	15	50	10	5.00	3,543.75	9.00	3,862.69
场地整平、表面垃圾清	25		3.78	5.00	1,359.90	9.00	1,482.29
高压注浆	20	52	10	5.00	861.00	9.00	938.49
聚氨酯防水一遍	20.66	10.51	2.33	5.00	1,583.10	9.00	1,725.58
垃圾清理外运	157		1276	5.00	1,504.65	9.00	1,640.07
去灰型底油	2	3	12.56	5.00	829.80	9.00	904.48
钻洞并装置注浆针头	2	5	1	5.00	84.00	9.00	91.56
169单元西面外墙空鼓开裂	303.76	136.54	1304.38	5.00	14,501.19	9.00	15,806.31
安装	17	22.7	8	5.00	1,903.42	9.00	2,074.73
打开墙面	31		2.43	5.00	1,333.80	9.00	1,453.84
底层抹灰	12	15.48	2	5.00	1,176.10	9.00	1,281.95
刮腻子	9	11	0.63	5.00	823.08	9.00	897.16
挂网	9	2.7	0.56	5.00	545.69	9.00	594.80
抗裂砂浆整体批刮	11	12.4	1.3	5.00	1,099.86	9.00	1,198.85
垃圾清理外运	157		1276	5.00	1,504.65	9.00	1,640.07
刷墙固	11	12	2.3	5.00	1,126.57	9.00	1,227.96
刷外墙涂料	46.76	60.26	11.16	5.00	4,988.02	9.00	5,436.95