

天鹅湖花园B区房屋渗水维修工程预算

行标签	求和项:数量	求和项:人工	求和项:主材	求和项:机械辅材	平均值项:综合取费	求和项:不含税单价	平均值项:税率	求和项:含税合价:J
106	1975.27	610.54	1128.06	865.84	5.00	2,734.66	9.00	81,474.19
防水基面清理	381	35.04		11.56	5.00	48.94	9.00	10,162.15
对原防水卷材和水泥砂浆保护层铲除、凿除表面松动部位	381	35.04		11.56	5.00	48.94	9.00	10,162.15
沟槽堵漏	25.9	54.7	62.5	5.48	5.00	128.82	9.00	1,818.36
堵漏王隔水	25.9	54.7	62.5	5.48	5.00	128.82	9.00	1,818.36
沟槽防水	25.9	37.42	59.42	6.24	5.00	108.24	9.00	1,527.86
聚氨酯防水涂料	25.9	37.42	59.42	6.24	5.00	108.24	9.00	1,527.86
沟槽回填	2.22	153.72	860.5	75.74	5.00	1,144.46	9.00	1,384.70
混凝土回填	2.22	153.72	860.5	75.74	5.00	1,144.46	9.00	1,384.70
基础处理	381	14.74	6.88	1.32	5.00	24.08	9.00	5,000.09
对沿水落口、接缝处及太阳能底座基础等部位涂刷基层处理剂	381	14.74	6.88	1.32	5.00	24.08	9.00	5,000.09
聚氨酯封边	95.25	33.54	43.3	4.52	5.00	85.42	9.00	4,434.26
搭接处聚氨酯封边	95.25	33.54	43.3	4.52	5.00	85.42	9.00	4,434.26
开槽	37	51.1	0	24.5	5.00	79.38	9.00	1,600.70
宽20cm, 深30cm	37	51.1	0	24.5	5.00	79.38	9.00	1,600.70
垃圾清理	254	26.32		7.04	5.00	35.02	9.00	4,847.82
人工清理建筑垃圾并装袋, 垂直运输短驳	254	26.32		7.04	5.00	35.02	9.00	4,847.82
垃圾外运	11	100		720	5.00	861.00	9.00	5,161.70
自卸汽车运土(8t以内)(运距25km以内)	11	100		720	5.00	861.00	9.00	5,161.70
铺防水卷材	381	61.62	75.72	4.82	5.00	149.26	9.00	30,993.10
铺贴东方雨虹3mm厚SBS防水卷材, 搭接150mm	381	61.62	75.72	4.82	5.00	149.26	9.00	30,993.10
做防水一遍	381	42.34	19.74	4.62	5.00	70.04	9.00	14,543.45
对卷材基层面涂刷PBC328非固化橡胶沥青防水涂料	381	42.34	19.74	4.62	5.00	70.04	9.00	14,543.45

