

天鹅湖花园B区房屋渗水维修工程预算

行标签	求和项:数量	求和项:人工	求和项:主材	求和项:机械辅材	平均值项:综合取费	求和项:不含税单价	平均值项:税率	求和项:含税合价:J
97	1363.59	1342.19	1599.71	1997.68	5.00	5,186.53	9.00	60,321.33
表面清理	67.8	62.24		9.72	5.00	75.56	9.00	1,396.01
对原墙面落灰、起皮的地方进行铲除	67.8	62.24		9.72	5.00	75.56	9.00	1,396.01
窗口打胶	4	380.68	760.84	49.64	5.00	1,250.72	9.00	1,363.28
窗口原密封胶铲除,重新打硅宝结构耐候胶	4	380.68	760.84	49.64	5.00	1,250.72	9.00	1,363.28
大理石缝隙处打胶	101.7	48	60	16	5.00	130.20	9.00	3,608.26
大理石原密封胶铲除,重新打硅宝结构耐候胶	101.7	48	60	16	5.00	130.20	9.00	3,608.26
防水基面清理	174	17.52		5.78	5.00	24.47	9.00	4,640.98
对原防水卷材和水泥砂浆保护层铲除、凿除表面松动部位	174	17.52		5.78	5.00	24.47	9.00	4,640.98
沟槽堵塞	12.95	27.35	31.25	2.74	5.00	64.41	9.00	909.18
堵塞王隔水	12.95	27.35	31.25	2.74	5.00	64.41	9.00	909.18
沟槽防水	12.95	18.71	29.71	3.12	5.00	54.12	9.00	763.93
聚氨酯防水涂料	12.95	18.71	29.71	3.12	5.00	54.12	9.00	763.93
沟槽回填	1.11	76.86	430.25	37.87	5.00	572.23	9.00	692.35
混凝土回填	1.11	76.86	430.25	37.87	5.00	572.23	9.00	692.35
基础处理	174	7.37	3.44	0.66	5.00	12.04	9.00	2,283.51
对沿水落口、接缝处及太阳能底座基础等部位涂刷基层处理剂	174	7.37	3.44	0.66	5.00	12.04	9.00	2,283.51
接缝处打胶	94.92	141	86.08	16.84	5.00	256.12	9.00	6,624.72
对大理石与外墙面接缝处,原密封胶铲除,重新打硅宝结构胶	94.92	141	86.08	16.84	5.00	256.12	9.00	6,624.72
聚氨酯封边	43.5	16.77	21.65	2.26	5.00	42.71	9.00	2,025.10
搭接处聚氨酯封边	43.5	16.77	21.65	2.26	5.00	42.71	9.00	2,025.10
开槽	18.5	25.55	0	12.25	5.00	39.69	9.00	800.35
宽20cm,深30cm	18.5	25.55	0	12.25	5.00	39.69	9.00	800.35
垃圾清理	150	65.8		17.6	5.00	87.55	9.00	2,862.90
人工清理建筑垃圾并装袋,垂直运输短驳	150	65.8		17.6	5.00	87.55	9.00	2,862.90
垃圾外运	11	250		1800	5.00	2,152.50	9.00	5,161.72
自卸汽车运土(8t以内)(运距25km以内)	11	250		1800	5.00	2,152.50	9.00	5,161.72
铺防水卷材	174	30.81	37.86	2.41	5.00	74.63	9.00	14,154.33
铺贴东方雨虹3mm厚SBS防水卷材,搭接150mm	174	30.81	37.86	2.41	5.00	74.63	9.00	14,154.33
涂刷防水涂料2遍	74.58	133.28	98.16	13.44	5.00	257.12	9.00	5,225.46
涂刷东方雨虹HCA121透明防水涂料	74.58	133.28	98.16	13.44	5.00	257.12	9.00	5,225.46
涂刷界面剂	74.58	19.08	30.6	5.04	5.00	57.44	9.00	1,167.36
德高界面处理剂	74.58	19.08	30.6	5.04	5.00	57.44	9.00	1,167.36
做防水一遍	174	21.17	9.87	2.81	5.00	35.02	9.00	6,641.89
对卷材基层面涂刷PBC328非固化橡胶沥青防水涂料	174	21.17	9.87	2.81	5.00	35.02	9.00	6,641.89

