

行标签	求和项:数量:A	求和项:人工费(不含税):B	求和项:主材费(求和项:机械辅材费(求和项:综合取费(求和项:不含税:求和项:不含税:求和项:税率:求和项:含税单价:J	求和项:不含税:求和项:含税:求和项:含税单价:J						
124-101南客厅阳台外墙漏水	124	2483.28	5281.38	5523.02	6015.73	735.00	17,661.06	94,015.74	1,323.00	102,477.19
窗口原密封胶铲除,重新打硅宝结构耐候胶	116.36	259.23	258.92	391.19	40.00	5.00	954.80	5,452.87	72.00	5,943.63
对原墙面落灰、起皮的地方进行铲除	2	95.17	190.21	12.41	12.41	5.00	312.68	625.36	9.00	681.64
德高界面处理剂	26.4	12	15	4	5.00	5.00	32.55	859.32	9.00	936.66
对窗台与外墙面接缝处,原密封胶铲除,重新打硅宝结构	19.36	4.77	7.65	1.26	5.00	5.00	14.36	278.01	9.00	303.03
对原墙面落灰、起皮的地方进行铲除	24.64	35.25	21.52	4.21	5.00	5.00	64.03	1,577.70	9.00	1,719.69
人工清理建筑垃圾并装袋,垂直运输短驳	17.6	15.56	13.16	3.52	5.00	5.00	18.89	332.46	9.00	362.38
涂刷东方雨虹HCA121透明防水涂料	6	13.16	17.51	105.06	5.00	5.00	17.51	105.06	9.00	114.52
涂刷东方雨虹HCA121透明防水涂料	19.36	33.32	24.54	3.36	5.00	5.00	64.28	1,244.46	9.00	1,356.46
自卸汽车运土(8t以内)(运距25km以内)	1	50	360	402.61	50.00	5.00	430.50	4,305.00	9.00	4,692.25
124-1304南主卧外墙漏水	105.69	364.21	391.87	135.14	12.56	5.00	276.60	2,766.00	9.00	3,041.49
采用YH东方雨虹对缝隙堵漏	1	115.73	190.21	12.41	12.41	5.00	312.68	3,126.80	9.00	3,440.82
窗口原密封胶铲除,重新打硅宝结构耐候胶	1	95.17	190.21	12.41	12.41	5.00	312.68	3,126.80	9.00	3,440.82
德高界面处理剂	20.24	4.77	7.65	1.26	5.00	5.00	14.36	290.65	9.00	316.81
对窗台与外墙面接缝处,原密封胶铲除,重新打硅宝结构	5.52	12	15	4	5.00	5.00	32.55	179.68	9.00	195.85
对原墙面落灰、起皮的地方进行铲除	18.4	15.56	13.16	3.52	5.00	5.00	18.89	347.58	9.00	378.86
人工清理建筑垃圾并装袋,垂直运输短驳	6	13.16	17.51	105.06	5.00	5.00	17.51	114.52	9.00	114.52
水泥砂浆抹灰	11.04	20.66	10.51	2.33	5.00	5.00	35.18	388.39	9.00	423.35
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	20.24	28.6	21.2	2.13	5.00	5.00	54.53	1,103.69	9.00	1,203.02
外墙溶剂涂料一底二面	21.25	8.56	12.16	1.97	5.00	5.00	23.82	506.18	9.00	551.74
自卸汽车运土(8t以内)(运距25km以内)	1	50	360	402.61	50.00	5.00	430.50	4,305.00	9.00	4,692.25
124-1901客厅北外墙漏水	110.9	364.21	391.87	135.14	12.56	5.00	276.60	2,766.00	9.00	3,041.49
采用YH东方雨虹对缝隙堵漏	2	115.73	190.21	12.41	12.41	5.00	312.68	3,126.80	9.00	3,440.82
窗口原密封胶铲除,重新打硅宝结构耐候胶	1	95.17	190.21	12.41	12.41	5.00	312.68	3,126.80	9.00	3,440.82
德高界面处理剂	21.12	4.77	7.65	1.26	5.00	5.00	14.36	303.28	9.00	330.58
对窗台与外墙面接缝处,原密封胶铲除,重新打硅宝结构	5.76	12	15	4	5.00	5.00	32.55	187.49	9.00	204.36
对原墙面落灰、起皮的地方进行铲除	19.2	15.56	13.16	3.52	5.00	5.00	18.89	362.69	9.00	395.33
人工清理建筑垃圾并装袋,垂直运输短驳	6	13.16	17.51	105.06	5.00	5.00	17.51	105.06	9.00	114.52
水泥砂浆抹灰	11.52	20.66	10.51	2.33	5.00	5.00	35.18	405.27	9.00	441.74
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.12	28.6	21.2	2.13	5.00	5.00	54.53	1,151.67	9.00	1,255.32
外墙溶剂涂料一底二面	22.18	8.56	12.16	1.97	5.00	5.00	23.82	528.33	9.00	575.88
自卸汽车运土(8t以内)(运距25km以内)	1	50	360	402.61	50.00	5.00	430.50	4,305.00	9.00	4,692.25
124-2001南主卧外墙漏水	110.9	364.21	391.87	135.14	12.56	5.00	276.60	2,766.00	9.00	3,041.49
采用YH东方雨虹对缝隙堵漏	2	115.73	190.21	12.41	12.41	5.00	312.68	3,126.80	9.00	3,440.82
窗口原密封胶铲除,重新打硅宝结构耐候胶	1	95.17	190.21	12.41	12.41	5.00	312.68	3,126.80	9.00	3,440.82
德高界面处理剂	21.12	4.77	7.65	1.26	5.00	5.00	14.36	303.28	9.00	330.58
对窗台与外墙面接缝处,原密封胶铲除,重新打硅宝结构	5.76	12	15	4	5.00	5.00	32.55	187.49	9.00	204.36
对原墙面落灰、起皮的地方进行铲除	19.2	15.56	13.16	3.52	5.00	5.00	18.89	362.69	9.00	395.33
人工清理建筑垃圾并装袋,垂直运输短驳	6	13.16	17.51	105.06	5.00	5.00	17.51	105.06	9.00	114.52
水泥砂浆抹灰	11.52	20.66	10.51	2.33	5.00	5.00	35.18	405.27	9.00	441.74
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	21.12	28.6	21.2	2.13	5.00	5.00	54.53	1,151.67	9.00	1,255.32
外墙溶剂涂料一底二面	22.18	8.56	12.16	1.97	5.00	5.00	23.82	528.33	9.00	575.88
自卸汽车运土(8t以内)(运距25km以内)	1	50	360	402.61	50.00	5.00	430.50	4,305.00	9.00	4,692.25
124-2002南主卧外墙漏水	130.24	364.21	391.87	135.14	12.56	5.00	276.60	2,766.00	9.00	3,041.49
采用YH东方雨虹对缝隙堵漏	2	115.73	190.21	12.41	12.41	5.00	312.68	3,126.80	9.00	3,440.82
窗口原密封胶铲除,重新打硅宝结构耐候胶	1	95.17	190.21	12.41	12.41	5.00	312.68	3,126.80	9.00	3,440.82
德高界面处理剂	24.75	4.77	7.65	1.26	5.00	5.00	14.36	355.41	9.00	387.40
对窗台与外墙面接缝处,原密封胶铲除,重新打硅宝结构	6.75	12	15	4	5.00	5.00	32.55	219.71	9.00	239.48
对原墙面落灰、起皮的地方进行铲除	22.5	15.56	13.16	3.52	5.00	5.00	18.89	425.03	9.00	463.28
人工清理建筑垃圾并装袋,垂直运输短驳	8	13.16	10.51	2.33	5.00	5.00	17.51	140.08	9.00	152.69
水泥砂浆抹灰	13.5	20.66	10.51	2.33	5.00	5.00	35.18	474.93	9.00	517.67
涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	24.75	28.6	21.2	2.13	5.00	5.00	54.53	1,349.62	9.00	1,471.09
外墙溶剂涂料一底二面	25.99	8.56	12.16	1.97	5.00	5.00	23.82	619.08	9.00	674.80
自卸汽车运土(8t以内)(运距25km以内)	1	50	360	402.61	50.00	5.00	430.50	4,305.00	9.00	4,692.25

124-2101客厅阳台南外墙漏水	采用YH东方雨虹对缝隙堵漏	134.97	364.21	391.87	402.61	50.00	1,216.62	5,018.00	90.00	5,489.63
	窗口原密封胶铲除,重新打硅宝结构耐候胶	2	115.73	135.14	12.56	5.00	276.60	553.20	9.00	602.99
	德高界面处理剂	1	95.17	190.21	12.41	5.00	312.68	312.68	9.00	340.82
	对窗台与外墙面接缝处,原密封胶铲除,重新打硅宝结构	25.74	4.77	7.65	1.26	5.00	14.36	369.63	9.00	402.90
	对原墙面落灰、起皮的地方进行铲除	7.02	12	15	4	5.00	32.55	228.50	9.00	249.07
	人工清理建筑垃圾并装袋,垂直运输短驳	23.4	15.56		2.43	5.00	18.89	442.03	9.00	481.81
	水泥砂浆抹灰	8	13.16		3.52	5.00	17.51	140.08	9.00	152.69
	涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	14.04	20.66	10.51	2.33	5.00	35.18	493.93	9.00	538.38
	外墙溶剂涂料一底二面	25.74	28.6	21.2	2.13	5.00	54.53	1,403.60	9.00	1,529.92
	自卸汽车运土(8t以内)(运距25km以内)	27.03	8.56	12.16	1.97	5.00	23.82	643.85	9.00	701.80
124-2101主卧南外墙漏水	采用YH东方雨虹对缝隙堵漏	125.51	364.21	391.87	402.61	50.00	1,216.62	5,037.63	90.00	5,491.02
	窗口原密封胶铲除,重新打硅宝结构耐候胶	2	115.73	135.14	12.56	5.00	276.60	553.20	9.00	602.99
	德高界面处理剂	23.76	4.77	7.65	1.26	5.00	312.68	625.36	9.00	681.64
	对窗台与外墙面接缝处,原密封胶铲除,重新打硅宝结构	6.48	12	15	4	5.00	32.55	210.92	9.00	371.90
	对原墙面落灰、起皮的地方进行铲除	21.6	15.56		2.43	5.00	18.89	408.02	9.00	444.74
	人工清理建筑垃圾并装袋,垂直运输短驳	7	13.16		3.52	5.00	17.51	122.57	9.00	133.60
	水泥砂浆抹灰	12.96	20.66	10.51	2.33	5.00	35.18	455.93	9.00	496.96
	涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	23.76	28.6	21.2	2.13	5.00	54.53	1,295.63	9.00	1,412.24
	外墙溶剂涂料一底二面	24.95	8.56	12.16	1.97	5.00	23.82	594.31	9.00	647.80
	自卸汽车运土(8t以内)(运距25km以内)	1	50		360	5.00	430.50	430.50	9.00	469.25
124-2102主卧南外墙漏水	采用YH东方雨虹对缝隙堵漏	130.24	364.21	391.87	402.61	50.00	1,216.62	4,880.24	90.00	5,319.47
	窗口原密封胶铲除,重新打硅宝结构耐候胶	2	115.73	135.14	12.56	5.00	276.60	553.20	9.00	602.99
	德高界面处理剂	24.75	4.77	7.65	1.26	5.00	312.68	312.68	9.00	340.82
	对窗台与外墙面接缝处,原密封胶铲除,重新打硅宝结构	6.75	12	15	4	5.00	32.55	219.71	9.00	387.40
	对原墙面落灰、起皮的地方进行铲除	22.5	15.56		2.43	5.00	18.89	425.03	9.00	239.48
	人工清理建筑垃圾并装袋,垂直运输短驳	8	13.16		3.52	5.00	17.51	140.08	9.00	152.69
	水泥砂浆抹灰	13.5	20.66	10.51	2.33	5.00	35.18	474.93	9.00	517.67
	涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	24.75	28.6	21.2	2.13	5.00	54.53	1,349.62	9.00	1,471.09
	外墙溶剂涂料一底二面	25.99	8.56	12.16	1.97	5.00	23.82	619.08	9.00	674.80
	自卸汽车运土(8t以内)(运距25km以内)	1	50		360	5.00	430.50	430.50	9.00	469.25
124-2203主卧东侧面外墙漏水	160PVC管道安装	126.41	494.83	488.84	416.28	60.00	1,469.94	5,170.44	108.00	5,635.78
	160PVC直接安装	2	95.17	81.62	12.41	5.00	198.66	397.32	9.00	433.08
	采用YH东方雨虹对缝隙堵漏	2	35.45	15.35	1.26	5.00	54.66	109.32	9.00	119.16
	窗口原密封胶铲除,重新打硅宝结构耐候胶	1	115.73	135.14	12.56	5.00	276.60	553.20	9.00	602.99
	德高界面处理剂	23.32	95.17	190.21	12.41	5.00	312.68	312.68	9.00	340.82
	对窗台与外墙面接缝处,原密封胶铲除,重新打硅宝结构	6.36	12	15	4	5.00	14.36	334.88	9.00	365.07
	对原墙面落灰、起皮的地方进行铲除	21.2	15.56		2.43	5.00	32.55	207.02	9.00	225.65
	人工清理建筑垃圾并装袋,垂直运输短驳	7	13.16		3.52	5.00	18.89	400.47	9.00	436.51
	水泥砂浆抹灰	12.72	20.66	10.51	2.33	5.00	35.18	447.49	9.00	487.76
	涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料	23.32	28.6	21.2	2.13	5.00	54.53	1,271.64	9.00	1,386.09
124-2203天台屋面漏水	外墙溶剂涂料一底二面	24.49	8.56	12.16	1.97	5.00	23.82	583.35	9.00	635.85
	自卸汽车运土(8t以内)(运距25km以内)	1	50		360	5.00	430.50	430.50	9.00	469.25
	搭设外架钢管封边	772	156.8	72.82	376.94	35.00	636.88	28,440.19	63.00	30,999.81
	对卷材基层面涂刷PVC328非固化橡胶沥青防水涂料	39	16.77	21.65	2.26	5.00	42.71	1,665.69	9.00	1,815.60
	对沿水落口、接缝处及太阳能底座基础等部位涂刷基层处	156	21.17	9.87	2.31	5.00	35.02	5,463.12	9.00	5,954.80
	对原防水卷材和水泥砂浆保护层铲除、凿除表面松动部位	156	7.37	3.44	0.66	5.00	12.04	1,878.24	9.00	2,047.28
	铺贴东方雨虹3mm厚SBS防水卷材,搭接150mm	156	17.52	5.78	5.78	5.00	24.47	3,817.32	9.00	4,160.88
	人工清理建筑垃圾并装袋,垂直运输短驳	104	30.81	37.85	2.41	5.00	74.63	11,642.28	9.00	12,690.09
	自卸汽车运土(8t以内)(运距25km以内)	5	13.16		3.52	5.00	17.51	1,821.04	9.00	1,984.93
		127.19	364.21	391.87	402.61	50.00	430.50	2,152.50	9.00	2,346.23
124-302主卧南外墙漏水							1,216.62	4,555.54	90.00	4,965.53



采用YH东方雨虹对缝隙堵漏 窗口原密封胶铲除，重新打硅宝结构耐候胶 德高界面处理剂 对窗台与外墙面交接处，原密封胶铲除，重新打硅宝结构 对原墙面落灰、起皮的地方进行铲除 人工清理建筑垃圾并装袋，垂直运输短驳 水泥砂浆抹灰 涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料 外墙溶剂涂料一底二面 自卸汽车运土（8t以内）（运距25km以内）	1	115.73	135.14	12.56	5.00	276.60	276.60	9.00	301.49
	1	95.17	190.21	12.41	5.00	312.68	312.68	9.00	340.82
	24.53	4.77	7.65	1.26	5.00	14.36	352.25	9.00	383.95
	6.69	12	15	4	5.00	32.55	217.76	9.00	237.36
	22.3	15.56		2.43	5.00	18.89	421.25	9.00	459.16
	7	13.16		3.52	5.00	17.51	122.57	9.00	133.60
	13.38	20.66	10.51	2.33	5.00	35.18	470.71	9.00	513.07
	24.53	28.6	21.2	2.13	5.00	54.53	1,337.62	9.00	1,458.01
	25.76	8.56	12.16	1.97	5.00	23.82	613.60	9.00	668.82
	1	50		360	5.00	430.50	430.50	9.00	469.25
124-403南卧窗外墙漏水 采用YH东方雨虹对缝隙堵漏 窗口原密封胶铲除，重新打硅宝结构耐候胶 德高界面处理剂 对窗台与外墙面交接处，原密封胶铲除，重新打硅宝结构 对原墙面落灰、起皮的地方进行铲除 人工清理建筑垃圾并装袋，垂直运输短驳 水泥砂浆抹灰 涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料 外墙溶剂涂料一底二面 自卸汽车运土（8t以内）（运距25km以内）	131.81	364.21	391.87	402.61	50.00	1,216.62	4,925.99	90.00	5,369.33
	2	115.73	135.14	12.56	5.00	276.60	553.20	9.00	602.99
	1	95.17	190.21	12.41	5.00	312.68	312.68	9.00	340.82
	25.08	4.77	7.65	1.26	5.00	14.36	360.15	9.00	392.56
	6.84	12	15	4	5.00	32.55	222.64	9.00	242.68
	22.8	15.56		2.43	5.00	18.89	430.69	9.00	469.45
	8	13.16		3.52	5.00	17.51	140.08	9.00	152.69
	13.68	20.66	10.51	2.33	5.00	35.18	481.26	9.00	524.57
	25.08	28.6	21.2	2.13	5.00	54.53	1,367.61	9.00	1,490.69
	26.33	8.56	12.16	1.97	5.00	23.82	627.18	9.00	683.63
124-401次卧北外墙漏水 采用YH东方雨虹对缝隙堵漏 窗口原密封胶铲除，重新打硅宝结构耐候胶 德高界面处理剂 对窗台与外墙面交接处，原密封胶铲除，重新打硅宝结构 对原墙面落灰、起皮的地方进行铲除 人工清理建筑垃圾并装袋，垂直运输短驳 水泥砂浆抹灰 涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料 外墙溶剂涂料一底二面 自卸汽车运土（8t以内）（运距25km以内）	116.15	364.21	391.87	402.61	50.00	1,216.62	4,234.02	90.00	4,615.07
	1	115.73	135.14	12.56	5.00	276.60	276.60	9.00	301.49
	1	95.17	190.21	12.41	5.00	312.68	312.68	9.00	340.82
	22.22	4.77	7.65	1.26	5.00	14.36	319.08	9.00	347.80
	6.06	12	15	4	5.00	32.55	197.25	9.00	215.00
	20.2	15.56		2.43	5.00	18.89	381.58	9.00	415.92
	7	13.16		3.52	5.00	17.51	122.57	9.00	133.60
	12.12	20.66	10.51	2.33	5.00	35.18	426.38	9.00	464.75
	22.22	28.6	21.2	2.13	5.00	54.53	1,211.66	9.00	1,320.71
	23.33	8.56	12.16	1.97	5.00	23.82	555.72	9.00	605.73
124-802客厅西侧外墙漏水 采用YH东方雨虹对缝隙堵漏 窗口原密封胶铲除，重新打硅宝结构耐候胶 德高界面处理剂 对窗台与外墙面交接处，原密封胶铲除，重新打硅宝结构 对原墙面落灰、起皮的地方进行铲除 人工清理建筑垃圾并装袋，垂直运输短驳 水泥砂浆抹灰 涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料 外墙溶剂涂料一底二面 自卸汽车运土（8t以内）（运距25km以内）	118.25	364.21	391.87	402.61	50.00	1,216.62	4,295.19	90.00	4,681.75
	1	115.73	135.14	12.56	5.00	276.60	276.60	9.00	301.49
	1	95.17	190.21	12.41	5.00	312.68	312.68	9.00	340.82
	22.66	4.77	7.65	1.26	5.00	14.36	325.40	9.00	354.69
	6.18	12	15	4	5.00	32.55	201.16	9.00	219.26
	20.6	15.56		2.43	5.00	18.89	389.13	9.00	424.15
	7	13.16		3.52	5.00	17.51	122.57	9.00	133.60
	12.36	20.66	10.51	2.33	5.00	35.18	434.82	9.00	473.95
	22.66	28.6	21.2	2.13	5.00	54.53	1,235.65	9.00	1,346.86
	23.79	8.56	12.16	1.97	5.00	23.82	566.68	9.00	617.68
124-402客厅西侧外墙漏水 采用YH东方雨虹对缝隙堵漏 窗口原密封胶铲除，重新打硅宝结构耐候胶 德高界面处理剂 对窗台与外墙面交接处，原密封胶铲除，重新打硅宝结构 对原墙面落灰、起皮的地方进行铲除 人工清理建筑垃圾并装袋，垂直运输短驳 水泥砂浆抹灰 涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料 外墙溶剂涂料一底二面 自卸汽车运土（8t以内）（运距25km以内）	126.66	364.21	391.87	402.61	50.00	1,216.62	4,504.04	90.00	4,909.41
	2	115.73	135.14	12.56	5.00	276.60	553.20	9.00	602.99
	0	95.17	190.21	12.41	5.00	312.68	312.68	9.00	340.82
	24.42	4.77	7.65	1.26	5.00	14.36	350.67	9.00	382.23
	6.66	12	15	4	5.00	32.55	216.78	9.00	236.25
	22.2	15.56		2.43	5.00	18.89	419.36	9.00	457.10
	7	13.16		3.52	5.00	17.51	122.57	9.00	133.60
	13.32	20.66	10.51	2.33	5.00	35.18	468.60	9.00	510.77
	24.42	28.6	21.2	2.13	5.00	54.53	1,331.62	9.00	1,451.47
	25.64	8.56	12.16	1.97	5.00	23.82	610.74	9.00	665.71
124-401次卧北外墙漏水 采用YH东方雨虹对缝隙堵漏 窗口原密封胶铲除，重新打硅宝结构耐候胶 德高界面处理剂 对窗台与外墙面交接处，原密封胶铲除，重新打硅宝结构 对原墙面落灰、起皮的地方进行铲除 人工清理建筑垃圾并装袋，垂直运输短驳 水泥砂浆抹灰 涂刷东方雨虹HCA-108屋面外墙高弹性防水涂料 外墙溶剂涂料一底二面 自卸汽车运土（8t以内）（运距25km以内）	1	50		360	5.00	430.50	430.50	9.00	469.25
	1	115.73	135.14	12.56	5.00	276.60	276.60	9.00	301.49
	1	95.17	190.21	12.41	5.00	312.68	312.68	9.00	340.82
	22.66	4.77	7.65	1.26	5.00	14.36	325.40	9.00	354.69
	6.18	12	15	4	5.00	32.55	201.16	9.00	219.26
	20.6	15.56		2.43	5.00	18.89	389.13	9.00	424.15
	7	13.16		3.52	5.00	17.51	122.57	9.00	133.60
	12.36	20.66	10.51	2.33	5.00	35.18	434.82	9.00	473.95
	22.66	28.6	21.2	2.13	5.00	54.53	1,235.65	9.00	1,346.86
	23.79	8.56	12.16	1.97	5.00	23.82	566.68	9.00	617.68

