

### 工程报价单

工程名称：城市花园二区2025第五批维修工程													项目对接：许小利13770717044													项目地址：无锡市滨湖区万顺路												
序号	分项工程名称	项目特征描述	主材采购方式	主材品牌	计量单位	工程量	金额（元）					综合单价	合价	备注																								
							人工	主材	辅材及机械	综合费	综合单价																											
<b>13区242单元102室一楼南院子顶部接缝处渗水</b>																																						
1	墙面拆除	1、剔凿外墙砖及保温层（宽100cm）	/	/	m²	8.00	89.00	0.00	0.00	7.12	96.12	768.96																										
2	清理基层	1、清理基层，露出基层墙面	/	/	m²	8.00	73.00	0.00	0.00	5.84	78.84	630.72																										
3	修补基层	1、墙面一般抹灰 2、水泥砂浆进行修补 3、外墙腻子进行修	/	/	m²	8.00	75.00	31.00	13.00	9.52	128.52	1028.16																										
4	防水处理	1、刷涂一遍界面剂 2、刷涂两遍防水涂料	/	/	m²	8.00	33.00	84.00	12.00	10.32	139.32	1114.56																										
5	喷涂底漆	1、喷涂一层底漆	/	/	m²	8.00	69.00	13.00	21.00	8.24	111.24	889.92																										
6	修补真石漆	1、根据原真石漆的颜色和纹理，选择合适的真石漆进行修补	/	/	m²	8.00	69.00	35.00	39.00	11.44	154.44	1235.52																										
清单分项合计											<b>5667.84</b>																											
税金（9%）											<b>510.11</b>																											
工程总造价											<b>6177.95</b>																											

<b>13区242单元201室南露台朝西墙面渗水、单元大厅顶上漏水、一楼和</b>																									
1	墙面拆除	1、剔凿外墙砖及保温层（宽100cm）	/	/	m²	18.00	89.00	0.00	0.00	7.12	96.12	1730.16													
2	清理基层	1、清理基层，露出基层墙面	/	/	m²	18.00	73.00	0.00	0.00	5.84	78.84	1419.12													
3	修补基层	1、墙面一般抹灰 2、水泥砂浆进行修补 3、外墙腻子进行修	/	/	m²	18.00	75.00	31.00	13.00	9.52	128.52	2313.36													
4	防水处理	1、刷涂一遍界面剂 2、刷涂两遍防水涂料	/	/	m²	18.00	33.00	84.00	12.00	10.32	139.32	2507.76													
5	喷涂底漆	1、喷涂一层底漆	/	/	m²	18.00	69.00	13.00	21.00	8.24	111.24	2002.32													
6	修补真石漆	1、根据原真石漆的颜色和纹理，选择合适的真石漆进行修补	/	/	m²	18.00	69.00	35.00	39.00	11.44	154.44	2779.92													
清单分项合计											<b>12752.64</b>														
税金（9%）											<b>1147.74</b>														
工程总造价											<b>13900.38</b>														
<b>13区242单元501室阁楼西面外墙渗水</b>																									
1	墙面拆除	1、剔凿外墙砖及保温层（宽100cm）	/	/	m²	8.00	89.00	0.00	0.00	7.12	96.12	768.96													
2	清理基层	1、清理基层，露出基层墙面	/	/	m²	8.00	73.00	0.00	0.00	5.84	78.84	630.72													
3	修补基层	1、墙面一般抹灰 2、水泥砂浆进行修补 3、外墙腻子进行修	/	/	m²	8.00	75.00	31.00	13.00	9.52	128.52	1028.16													
4	防水处理	1、刷涂一遍界面剂 2、刷涂两遍防水涂料	/	/	m²	8.00	33.00	84.00	12.00	10.32	139.32	1114.56													
5	喷涂底漆	1、喷涂一层底漆	/	/	m²	8.00	69.00	13.00	21.00	8.24	111.24	889.92													
6	修补真石漆	1、根据原真石漆的颜色和纹理，选择合适的真石漆进行修补	/	/	m²	8.00	69.00	35.00	39.00	11.44	154.44	1235.52													
清单分项合计											<b>5667.84</b>														
税金（9%）											<b>510.11</b>														
工程总造价											<b>6177.95</b>														